



**KU-RING-GAI PLANNING PANEL
TO BE HELD ON WEDNESDAY, 13 AUGUST 2008 AT 5.00PM
LEVEL 3, COUNCIL CHAMBERS,
818 Pacific Highway, Gordon**

A G E N D A

**** ** * ** * ** ***

NOTE: For Full Details, See Council's Website –
www.kmc.nsw.gov.au under the link to business papers

APOLOGIES

DECLARATIONS OF INTEREST

CONFIRMATION OF REPORTS TO BE CONSIDERED IN CLOSED MEETING

ADDRESSES TO THE PANEL

DOCUMENTS CIRCULATED TO THE PANEL

CONFIRMATION OF MINUTES

Minutes of Ku-ring-gai Planning Panel

File: S06347

Meeting held 6 August 2008

Minutes to be circulated separately

MINUTES FROM THE CHAIRPERSON

PETITIONS

GENERAL BUSINESS

GB.1 **6 to 8 Culworth Avenue, Killara - Demolition of 2 Dwelling Houses & Construction of 3 Residential Flat Buildings comprising 63 Apartments & Basement Car Parking for 118 Cars**

File: DA0350/08

Ward: Gordon

Applicant: Culworth Avenue Pty Ltd

Owner: Culworth Avenue Pty Ltd

To determine Development Application No.0350/08 for the demolition of 2 dwelling houses and construction of 3 residential flat buildings comprising 63 apartments and car parking for 118 cars.

Recommendation:

THAT the Ku-ring-gai Planning Panel, as the consent authority, is of the opinion that the objection under *State Environmental Planning Policy no. 1- Development standards* to clause 25 L of the Ku-ring-gai Planning Scheme Ordinance to the zone interface standard is well founded. The Planning Panel is also of the opinion that strict compliance with the development standard is unreasonable and unnecessary in the circumstances of this case as there will be no appreciable affect upon amenity in terms of the adjoining site being zoned Special Uses-Municipal Purposes and that the reduction in set back to the zone interface will not have an adverse impact upon the local amenity and environmental character of the area.

AND

That the Ku-ring-gai Planning Panel, as the consent authority, grant development consent to DA0350/08 for the demolition of existing structures and the construction of a residential flat building (63 units), basement parking, landscaping and lot consolidation on land at Nos. 6-8 Culworth Avenue, Killara, for a period of two (2) years from the date of the Notice of Determination, subject to the following conditions:

CONDITIONS THAT IDENTIFY APPROVED PLANS:

1. Approved architectural plans and documentation (new development)

The development must be carried out in accordance with the following plans and documentation listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Plan no.	Drawn for	Dated
DA01	Culworth Avenue Pty Ltd	27.06.08
DA03A	Culworth Avenue Pty Ltd	27.06.08
DA04A	Culworth Avenue Pty Ltd	27.06.08
DA05A	Culworth Avenue Pty Ltd	27.06.08
DA06B	Culworth Avenue Pty Ltd	27.06.08
DA07B	Culworth Avenue Pty Ltd	27.06.08
DA08A	Culworth Avenue Pty Ltd	27.06.08
DA09A	Culworth Avenue Pty Ltd	27.06.08
DA10A	Culworth Avenue Pty Ltd	27.06.08
DA11A	Culworth Avenue Pty Ltd	27.06.08
DA12A	Culworth Avenue Pty Ltd	27.06.08
DA13A	Culworth Avenue Pty Ltd	27.06.08
DA14A	Culworth Avenue Pty Ltd	27.06.08
DA15A	Culworth Avenue Pty Ltd	27.06.08
TC001	Culworth Avenue Pty Ltd	27.06.08
TC002	Culworth Avenue Pty Ltd	27.06.08
SH01A	Culworth Avenue Pty Ltd	27.06.08
SH02A	Culworth Avenue Pty Ltd	27.06.08
SH03A	Culworth Avenue Pty Ltd	27.06.08
SH04A	Culworth Avenue Pty Ltd	27.06.08
SH05A	Culworth Avenue Pty Ltd	27.06.08
SH06A	Culworth Avenue Pty Ltd	27.06.08
C01	Culworth Avenue Pty Ltd	14.07.08
05.08/040 Rev C	i Scape	24.06.08

Document(s)	Dated
Basix Certificate No.205913M	14 July, 2008

Reason: To ensure that the development is in accordance with the determination.

2. Inconsistency between documents

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent prevail.

Reason: To ensure that the development is in accordance with the determination.

3. Approved landscape plans

Landscape works shall be carried out in accordance with the following landscape plan(s), listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

Plan no.	Drawn by	Dated
05.08/040 Rev C	iScape	24/06/08

Reason: To ensure that the development is in accordance with the determination.

CONDITIONS TO BE SATISFIED PRIOR TO DEMOLITION, EXCAVATION OR CONSTRUCTION:

3A. Surrender of development consent

The applicant must surrender the following development consent to Council by

submitting a completed copy of Form 3 of the Environmental Planning and Assessment Regulation 2000.

Development Consent No.	Dated	For:
DA1369/04	29 August 2005	Demolition of 2 residential dwelling houses and construction of 3 x 5 storey residential flat buildings comprising 54 units and basement car parking for 101 vehicles.

Reason: To ensure that there is certainty as to the consent applying to the subject land.

4. Dilapidation survey and report (public infrastructure)

Prior to the commencement of any development or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures of the following public infrastructure, has been completed and submitted to Council:

Public infrastructure

- Full road pavement width, including kerb and gutter, of Culworth Avenue over the site frontage.
- All driveway crossings and laybacks opposite the subject site.

The report must be completed by a consulting structural/civil engineer. Particular attention must be paid to accurately recording (both written and photographic) existing damaged areas on the aforementioned infrastructure so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development.

The developer may be held liable to any recent damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded by the requirements of this condition prior to the commencement of works.

Note: A written acknowledgment from Council must be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any excavation works.

Reason: To record the structural condition of public infrastructure before works commence.

5. Dilapidation survey and report (private property)

Prior to the commencement of any demolition or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures upon the following lands, has been completed and submitted to Council:

Address

- 4, 10 and 12 Culworth Avenue, and the tennis court at 2 Culworth Avenue.

The dilapidation report must include a photographic survey of adjoining properties detailing their physical condition, both internally and externally, including such items as walls ceilings, roof and structural members. The report must be completed by a consulting structural/geotechnical engineer as determined necessary by that professional based on the excavations for the proposal and the recommendations of the submitted geotechnical report.

In the event that access for undertaking the dilapidation survey is denied by a property owner, the applicant must demonstrate in writing to the satisfaction of the Principal Certifying Authority that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed.

Note: A copy of the dilapidation report is to be provided to Council prior to any excavation works been undertaken. The dilapidation report is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any civil action required to resolve any dispute over damage to adjoining properties arising from works.

Reason: To record the structural condition of likely affected properties before works commence.

5A. Archival recording of buildings

Prior to the commencement of any development or excavation works on site, the Principal Certifying Authority shall be satisfied that an archival report has been submitted to Council's Heritage Advisor.

The report must consist of an archival standard photographic record of the building (internally and externally), its garden and views of it from the street illustrating its relationship to neighbouring properties and the streetscape. Recording shall be undertaken in accordance with the guidelines for "Photographic Recording of Heritage Items Using Film or Digital Capture (2006)" prepared by the New South Wales Heritage Office.

Information shall be bound in an A4 report format. It shall include copies of photographs, referenced to plans of the site. Two (2) copies (one (1) copy to include negatives or CD of images shall be submitted to Council's Heritage Advisor. The recording document will be held in the local studies collection of Ku-ring-gai Library, the local historical society and Council's files.

Note: A written acknowledgment from Council must be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any works.

Reason: To ensure the proper management of historical artefacts and to ensure their preservation.

6. Construction and traffic management plan

Prior to the commencement of any works on site, the applicant must submit for review by Council's engineers a construction and traffic management plan. The following matters must be specifically addressed in the plan:

A plan view of the entire site and frontage roadways indicating:

- dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways
- turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site
- the locations of proposed work zones in the frontage roadways
- location of any proposed crane and concrete pump and truck standing areas on and off the site
- a dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries
- material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected
- an on-site parking area for employees, tradespersons and construction vehicles as far as possible

Traffic control plan(s) for the site

All traffic control plans must be in accordance with the RTA publication "Traffic Control Worksite Manual" and prepared by a suitably qualified person (minimum 'red card' qualification). The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each stage.

Approval is to be obtained from Council for any temporary road closures or crane use from public property. Applications to Council shall be made a minimum of 4 weeks prior to the activity proposed being undertaken.

A detailed description and route map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage must be provided.

Light traffic roads and those subject to a load or height limit must be avoided where alternate routes exist.

A copy of this route is to be made available to all contractors and shall be clearly depicted at a location within the site.

The plan must provide evidence of RTA concurrence where construction access is provided directly from or within 20m of an arterial road.

The plan must provide a schedule of site inductions to be held on regular occasions and as determined necessary to ensure all new employees are aware of their construction management obligations. These must specify that construction-related vehicles are to comply with the approved requirements.

The plan must provide measures for minimising construction related traffic movements during school peak periods.

For those construction personnel that drive to the site, the applicant shall attempt to provide on-site parking so that their personnel's vehicles do not impact on the current parking demand in the area.

The construction and traffic management plan shall be prepared by a suitably qualified and experienced traffic consultant and be certified by this person as being in accordance with the requirements of the abovementioned documents and the requirements of this condition. The construction management measures contained in the approved plan shall be implemented in accordance with the plan prior to the commencement of, and during, works on-site including excavation.

As the plan has a direct impact on the local road network, the plan shall be submitted to and reviewed by Council's Development Engineer. Written acknowledgment from Council's Engineer shall be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any works on site.

Reason: To ensure that appropriate measures have been considered during all phases of the construction process in a manner that maintains the environmental amenity and ensures the ongoing safety and protection of people.

7. Work zone

If a works zone is proposed, the applicant must make a written application to the Ku-ring-gai Local Traffic Committee to install the work zone. Work zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Work zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site.

If the work zone is approved by the Local Traffic Committee, the applicant must obtain a written copy of the related resolution from the Ku-ring-gai Local Traffic Committee and submit this to the Principal Certifying Authority prior to commencement of any works on site.

Where approval of the work zone is resolved by the Committee, the necessary work zone signage shall be installed (at the cost of the applicant) and the adopted fee paid prior to commencement of any works on site. At the expiration of the work zone approval, the applicant is required to remove the work zone signs and reinstate any previous signs at their expense.

In the event the work zone is required for a period beyond that initially approved by the Traffic Committee, the applicant shall make a payment to Council for the extended period in accordance with Council's schedule of fees and charges for work zones prior to the extended period commencing.

Reason: To ensure that appropriate measures have been made for the operation of the site during the construction phase.

8. Erosion and drainage management

Earthworks and/or demolition of any existing buildings shall not commence until an erosion and sediment control plan is submitted to and approved by the Principal Certifying Authority. The plan shall comply with the guidelines set out in the NSW Department of Housing manual "Managing Urban Stormwater: Soils and Construction" certificate. Erosion and sediment control works shall be implemented in accordance with the erosion and sediment control plan.

Reason: To preserve and enhance the natural environment.

9. Tree protection fencing

To preserve the following tree/s, no work shall commence until the area beneath their canopy is fenced off at the specified radius from the trunk/s to prevent any activities, storage or the disposal of materials within the fenced area. The fence/s shall be maintained intact until the completion of all demolition/building work on site.

Schedule

Tree/location

Radius in metres

#1 <i>Arecastrum romanzoffianum</i> (Coccos Palm) Adjacent to eastern/Culworth Ave site boundary	2.0m
#2 <i>Magnolia soulangeana</i> (Saucer Magnolia) Adjacent to eastern/Culworth Ave site boundary	3.0m
#3 <i>Nyssa sylvatica</i> (Tupelo) Adjacent to eastern/Culworth Ave site boundary	5.0m
#15 <i>Metasequoia glyptostroboides</i> (Dawn Redwood) Adjacent to southern site boundary in neighbouring property	3.0m
#22 <i>Euphorbia tirucalli</i> (Pencil Tree) Adjacent to western site boundary	3.0m
#26 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#27 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#28 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	3.0m
#30 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	2.0m
#31 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	2.0m
#32 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	2.0m
#33 <i>Howea forsteriana</i> (Kentia Palm) Adjacent to eastern site boundary	2.0m
#34 <i>Pittosporum undulatum</i> (Sweet Pittosporum) Adjacent to northern site boundary	4.0m
#35 <i>Syzigium luehmannii</i> (Lillypilly) Adjacent to northern site boundary	5.0m
#37 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to western site boundary	4.0m
#41 <i>Liquidambar styraciflua</i> (Sweet Gum) Adjacent to northern site boundary	4.0m
#44 <i>Ulmus spp.</i> (Elm) Adjacent to northern site boundary	4.0m
#46 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to western site boundary	3.0m

Schedule

Tree/location	Radius in metres
#47 <i>Eucalyptus saligna</i> (Sydney Bluegum) Adjacent to northeast site corner in neighbouring property	9.0m
#49 <i>Stenocarpus sinuatus</i> (Q'ld Firewheel Tree) Adjacent to eastern site boundary	3.0m
#50 <i>Jacaranda mimosifolia</i> (Jacaranda) Adjacent to eastern site boundary	4.0m
#54 <i>Jacaranda mimosifolia</i> (Jacaranda) Adjacent to northern site boundary in neighbouring property	4.0m
#55 <i>Acer palmatum</i> (Japanese Maple) Adjacent to northern site boundary in neighbouring property	4.0m
<i>Camellia sasanqua</i> hedge Adjacent to southern site boundary	1.0m

Reason: To protect existing trees during the construction phase.

10. Tree protection fencing excluding structure

To preserve the following tree/s, no work shall commence until the area beneath their canopy excluding that area of the proposed basement/residential flat building shall be fenced off for the specified radius from the trunk to prevent any activities, storage or the disposal of materials within the fenced area. The fence/s shall be maintained intact until the completion of all demolition/building work on site:

Schedule

Tree/location	Radius in metres
#10 <i>Ulmus parvifolia</i> (Chinese Elm) Adjacent to northern site boundary	6.0m

Reason: To protect existing trees during the construction phase.

11. Tree protection

If it is essential for scaffolding to be erected within a protected area, fencing should be erected to provide just sufficient space for scaffolding. The ground between this fence and the building should be protected by boarding (eg scaffold boards). A single thickness of boarding laid on the soil surface will provide sufficient protection for pedestrian loads, but more substantial boarding sufficient to spread the load should be used for heavier traffic. The ground beneath the boarding should be left undisturbed and should be protected with a porous geotextile fabric. If necessary, sand should be laid on the fabric to level the ground. When required, the building scaffolding should be erected. The boarding should be left in place until the building works are finished.

Reason: To protect existing trees during the construction phase.

12. Tree protection

If temporary vehicle access is required near a tree to be retained, 75x75x2000mm hardwood planks are to be lain over a mulched area to a depth of 100mm with organic material being 75% leaf litter and 25% wood to distribute weight and to minimise compaction of soil profiles beneath. Timber lengths are to be secured on top of such to avoid movement and the structure should be constructed to accommodate vehicles that are to be used on site. Structural soil or similar should be

used as a subgrade placed above existing soil levels for alternate driveway surfaces to support larger site vehicles or more rigid type temporary sealed road surfaces.

Reason: To protect existing trees during the construction phase.

13. Tree protection

Where tree protection measures are to be removed or altered this must be undertaken in consultation with the consultant Arborist to ensure tree protection is maintained.

Reason: To protect existing trees during the construction phase.

14. Tree Protective Fencing Type Galvanised Mesh

The tree protection fencing shall be constructed of galvanised pipe at 2.4 metre spacings and connected by securely attached chain mesh fencing to a minimum of 1.8 metres in height prior to work commencing.

Reason: To protect existing trees during construction phase.

15. Tree protection signage

Prior to works commencing, tree protection signage is to be attached to each tree protection zone, displayed in a prominent position and the sign repeated at 10 metres intervals or closer where the fence changes direction. Each sign shall contain in a clearly legible form, the following information:

- tree protection zone
- this fence has been installed to prevent damage to the trees and their growing environment both above and below ground and access is restricted
- any encroachment not previously approved within the tree protection zone shall be the subject of an arborist's report
- the arborist's report shall provide proof that no other alternative is available
- the arborist's report shall be submitted to the Principal Certifying Authority for further consultation with Council
- The name, address, and telephone number of the developer.

Reason: To protect existing trees during the construction phase.

16. Tree protection mulching

Prior to works commencing and throughout construction, the area of the tree protection zone is to be mulched to a depth of 100mm with composted organic material being 75% Eucalyptus leaf litter and 25% wood.

Reason: To protect existing trees during the construction phase.

17. Tree protection – avoiding soil compaction

To preserve the following tree/s and avoid soil compaction, no work shall commence until temporary measures to avoid soil compaction (eg rumble boards) beneath the canopy of the following tree/s is/are installed if vehicular access or repeated pedestrian access is required:

Schedule

Tree/Location

- #3 *Nyssa sylvatica* (Tupelo)
Adjacent to eastern/Culworth Ave site boundary
- #10 *Ulmus parvifolia* (Chinese Elm)
Adjacent to northern site boundary
- #15 *Metasequoia glyptostroboides* (Dawn Redwood)
Adjacent to southern site boundary in neighbouring property
- #28 *Eucalyptus acmeniodes* (White Mahogany)
Adjacent to western site boundary
- #41 *Liquidambar styraciflua* (Sweet Gum)
Adjacent to northern site boundary
- #44 *Ulmus spp.* (Elm)
Adjacent to northern site boundary
- #47 *Eucalyptus saligna* (Sydney Bluegum)
Adjacent to northeast site corner in neighbouring property
- #50 *Jacaranda mimosifolia* (Jacaranda)
Adjacent to eastern site boundary
- #54 *Jacaranda mimosifolia* (Jacaranda)
Adjacent to northern site boundary in neighbouring property
- #55 *Acer palmatum* (Japanese Maple)
Adjacent to northern site boundary in neighbouring property

Reason: To protect existing trees during the construction phase.

18. Tree fencing inspection

Upon installation of the required tree protection measures, an inspection of the site by the Principal Certifying Authority is required to verify that tree protection measures comply with all relevant conditions.

Reason: To protect existing trees during the construction phase.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE:

19. Consolidation of lots

Prior to issue of the Construction Certificate, the applicant must consolidate the existing Torrens title lots which will form the development site. Evidence of lot consolidation, in the form of a plan registered with Land and Property Information, must be submitted for approval of the Principal Certifying Authority prior to issue of the Construction Certificate.

Reason: To ensure that continuous structures will not be placed across separate titles.

20. Amendments to approved landscape plan

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that the approved landscape plans, listed below and endorsed with Council's stamp, have been amended in accordance with the requirements of this condition as well as other conditions of this consent:

Plan no.	Drawn by	Dated
05.08/040 Rev C	iScape	24/06/08

The above landscape plan(s) shall be amended in the following ways:

- To maintain neighbour and resident amenity, the existing *Camellia sasanqua* hedge adjacent to southern site boundary is to be retained. The correct location and extent of the hedge is to be shown on plan to ensure its retention (it is not located adjacent to the Culworth Avenue site frontage).
- To maintain and enhance landscape amenity an additional tall canopy tree able to attain a minimum height of 13.0m is to be planted adjacent to the site boundary to the north-western side of Unit CG02/north of Unit CG03.
- To maintain and enhance neighbour and resident amenity an additional tall canopy tree is to be planted adjacent to western site boundary adjacent to Unit CG05
- The proposed planting of a *Lagerstroemia indica* (Crepe Myrtle) adjacent to the northern site boundary is to be replaced with a tall canopy tree species able to attain a minimum height of 13.0m, or alternatively a tall canopy tree species is to be planted as a specimen planting within the proposed triangular lawn area.
- Proposed tree plantings at the time of planting are to have a minimum pot size of 75 litres to enhance the landscape setting.
- All external private courtyards with lawn areas are to have external access for maintenance purposes.

Prior to the issue of the Construction Certificate, the Principal Certifying Authority shall be satisfied that the landscape plan has been amended as required by this condition.

Note: An amended landscape plan, prepared by a landscape architect or qualified landscape designer shall be submitted to the Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

21. Long service levy

In accordance with Section 109F(i) of the Environmental Planning and Assessment Act a Construction Certificate shall not be issued until any long service levy payable under Section 34 of the Building and Construction Industry Long Service Payments Act 1986 (or where such levy is payable by instalments, the first instalment of the levy) has been paid. Council is authorised to accept payment. Where payment has been made elsewhere, proof of payment is to be provided to Council.

Reason: Statutory requirement.

22. Builder's indemnity insurance

The applicant, builder, developer or person who does the work on this development, must arrange builder's indemnity insurance and submit the certificate of insurance in accordance with the requirements of Part 6 of the Home Building Act 1989 to the Certifying Authority for endorsement of the plans accompanying the Construction Certificate.

It is the responsibility of the applicant, builder or developer to arrange the builder's indemnity insurance for residential building work over the value of \$12,000. The builder's indemnity insurance does not apply to commercial or industrial building work or to residential work valued at less than \$12,000, nor to work undertaken by persons holding an owner/builder's permit issued by the Department of Fair Trading (unless the owner/builder's property is sold within 7 years of the commencement of the work).

Reason: Statutory requirement.

23. Outdoor lighting

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that all outdoor lighting will comply with AS/NZ1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Note: Details demonstrating compliance with these requirements are to be submitted prior to the issue of a Construction Certificate.

Reason: To provide high quality external lighting for security without adverse affects on public amenity from excessive illumination levels.

24. Air drying facilities

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that a common open space area dedicated for open air drying of clothes is provided. This area is to be located at ground level behind the building line and in a position not visible from the public domain.

In lieu of the above, written confirmation that all units will be provided with internal clothes drying facilities prior to the Occupation Certificate is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Amenity & energy efficiency.

25. Access for people with disabilities (residential)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that access for people with disabilities to and from and between the public domain, residential units and all common open space areas is provided. Consideration must be given to the means of dignified and equitable access.

Compliant access provisions for people with disabilities shall be clearly shown on the plans submitted with the Construction Certificate. All details shall be provided to the Principal Certifying Authority prior to the issue of the Construction Certificate. All details shall be prepared in consideration of the Disability Discrimination Act, and the relevant provisions of AS1428.1, AS1428.2, AS1428.4 and AS 1735.12.

Reason: To ensure the provision of equitable and dignified access for all people in accordance with disability discrimination legislation and relevant Australian Standards.

26. Adaptable units

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that the nominated adaptable units within the development application, [enter unit nos.], are designed as adaptable housing in accordance with the provisions of Australian Standard AS4299-1995: Adaptable Housing.

Note: Evidence from an appropriately qualified professional demonstrating compliance with this control is to be submitted to and approved by the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Disabled access & amenity.

27. Stormwater management plan

Prior to issue of the Construction Certificate, the applicant must submit, for approval by the Principal Certifying Authority, scale construction plans and specifications in relation to the stormwater management and disposal system for the development. The plan(s) must include the following detail:

- exact location and reduced level of discharge point to the public drainage system
- Layout of the property drainage system components, including but not limited to (as required) gutters, downpipes, spreaders, pits, swales, kerbs, cut-off and intercepting drainage structures, subsoil drainage, flushing facilities and all ancillary stormwater plumbing - all designed for a 235mm/hour rainfall intensity for a duration of five (5) minutes (1:50 year storm recurrence)
- location(s), dimensions and specifications for the required rainwater storage and reuse tanks and systems and where proprietary products are to be used, manufacturer specifications or equivalent shall be provided
- specifications for reticulated pumping facilities (including pump type and manufacturer specifications) and ancillary plumbing to fully utilise rainwater in accordance with Ku-ring-gai Council Development Control Plan 47 and/or BASIX commitments
- details of the required on-site detention tanks required by Ku-ring-gai Water Management DCP 47, including dimensions, materials, locations, orifice and discharge control pit details as required (refer Chapter 6 and Appendices 2, 3 and 5 of DCP 47 for volume, PSD and design requirements)
- the required basement stormwater pump-out system is to cater for driveway runoff and subsoil drainage (refer appendix 7.1.1 of Development Control Plan 47 for design)
- measures are to be included in the design which will prevent backflow from the underground system in Selkirk Park entering the retention storage during times of high stormwater flows in Council's system.

The above construction drawings and specifications are to be prepared by a qualified and experienced civil/hydraulic engineer in accordance with Council's Water Management Development Control Plan 47, Australian Standards 3500.2 and 3500.3 - Plumbing and Drainage Code and the Building Code of Australia. The plans may be generally based on the Concept Stormwater Management Plan by ACOR Appleyard submitted with the development application, which are to be advanced as necessary for construction certificate issue purposes.

Reason: To protect the environment.

28. Stormwater retention

Prior to the issue of a Construction Certificate, the Principal Certifying Authority is to be satisfied that:

- A mandatory rainwater retention and re-use system, comprising storage tanks and ancillary plumbing is provided. The minimum total storage volume of the rainwater tank system, and the prescribed re-use of the water on site must satisfy all relevant BASIX commitments and the requirements specified in Chapter 6 of Ku-ring-gai Water Management Development Control Plan 47; and
- An on-site stormwater detention system must be provided to control the rate of runoff leaving the site. The minimum volume of the required on-site detention system must be determined in accordance with Chapter 6 of the Ku-ring-gai Council Water Management Development Control Plan 47 - having regard to the specified volume concession offered in lieu of installing rainwater retention tanks. The on-site detention system must be designed by a qualified civil/hydraulic engineer and must satisfy the design controls set out in Appendix 5 of DCP 47.

Reason: To protect the environment.

29. Driveway crossing levels

Prior to issue of the Construction Certificate, driveway and associated footpath levels for any new, reconstructed or extended sections of driveway crossings between the property boundary and road alignment must be obtained from Ku-ring-gai Council. Such levels are only able to be issued by Council under the Roads Act 1993. All footpath crossings, laybacks and driveways are to be constructed according to Council's specifications "Construction of Gutter Crossings and Footpath Crossings".

Specifications are issued with alignment levels after completing the necessary application form at Customer Services and payment of the assessment fee. When completing the request for driveway levels application from Council, the applicant must attach a copy of the relevant development application drawing which indicates the position and proposed level of the proposed driveway at the boundary alignment.

This development consent is for works wholly within the property. Development consent does not imply approval of footpath or driveway levels, materials or location within the road reserve, regardless of whether this information is shown on the development application plans. The grading of such footpaths or driveways outside the property shall comply with Council's standard requirements. The suitability of the grade of such paths or driveways inside the property is the sole responsibility of the applicant and the required alignment levels fixed by Council may impact upon these levels.

The construction of footpaths and driveways outside the property in materials other than those approved by Council is not permitted.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

30. Driveway grades – basement car parks

Prior to the issue of the Construction Certificate, longitudinal driveway sections are to be prepared by a qualified civil/traffic engineer and be submitted for to and approved by the Certifying Authority. These profiles are to be at 1:100 scale along both edges of the proposed driveway, starting from the centreline of the frontage street carriageway to the proposed basement floor level. The traffic engineer shall provide specific written certification on the plans that:

- vehicular access can be obtained using grades of 20% (1 in 5) maximum and
- all changes in grade (transitions) comply with Australian Standard 2890.1 – “Off-street car parking” (refer clause 2.5.3) to prevent the scraping of the underside of vehicles.

If a new driveway crossing is proposed, the longitudinal sections must incorporate the driveway crossing levels as issued by Council upon prior application.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

31. Basement car parking details

Prior to issue of the Construction Certificate, certified parking layout plan(s) to scale showing all aspects of the vehicle access and accommodation arrangements must be submitted to and approved by the Certifying Authority. A qualified civil/traffic engineer must review the proposed vehicle access and accommodation layout and provide written certification on the plans that:

- all parking space dimensions, driveway and aisle widths, driveway grades, transitions, circulation ramps, blind aisle situations and other trafficked areas comply with Australian Standard 2890.1 – 2004 “Off-street car parking”
- **a clear height clearance of 2.5 metres (required under DCP40 for waste collection trucks) is provided over the designated garbage collection truck manoeuvring areas within the basement**
- no doors or gates are provided in the access driveways to the basement car park which would prevent unrestricted access for internal garbage collection at any time from the basement garbage storage and collection area
- the vehicle access and accommodation arrangements are to be constructed and marked in accordance with the certified plans

Reason: To ensure that parking spaces are in accordance with the approved development.

32. Number of bicycle spaces

The basement car park shall be amended to provide 20 bicycle spaces in accordance with DCP 55. The bicycle parking spaces shall be designed in accordance with AS2890.3. Details shall be submitted to the satisfaction of the Certifying Authority prior to the issue of a Construction Certificate.

Reason: To provide alternative modes of transport to and from the site.

33. Design of works on Council infrastructure

Prior to issue of the Construction Certificate, the Certifying Authority shall be satisfied that engineering plans and specifications prepared by a qualified consulting engineer have been approved by Council's Development Engineer. The plans to be assessed must be to a detail suitable for construction issue purposes and must detail the following infrastructure works required in Selkirk Park:

- pipe within drainage easement and a junction pit over Council's underground stormwater drainage pipe.

Development consent does not give approval to these works in Council's reserve. The applicant must obtain a separate approval for the works required as part of the development. The Construction Certificate must not be issued, and these works must not proceed until Council has issued a formal written approval.

The required plans and specifications are to be designed in accordance with the General Specification for the Construction of Road and Drainage Works in Ku-ring-gai Council, dated November 2004. The drawings must detail existing utility services and trees affected by the works, erosion control requirements and traffic management requirements during the course of works. Survey must be undertaken as required. Traffic management is to be certified on the drawings as being in accordance with the documents SAA HB81.1 – 1996 – Field Guide for Traffic Control at Works on Roads – Part 1 and RTA Traffic Control at Work Sites (1998). Construction of the works must proceed only in accordance with any conditions attached to the approval issued by Council as the owner of Selkirk Park.

A minimum of three (3) weeks will be required for Council to assess the application. Early submission of the application is recommended to avoid delays in obtaining a Construction Certificate. An engineering assessment and inspection fee (set out in Council's adopted fees and charges) is payable and Council will withhold any consent and approved plans until full payment of the correct fees. Plans and specifications must be marked to the attention of Council's Development Engineers. In addition, a copy of this condition must be provided, together with a covering letter stating the full address of the property and the accompanying DA number.

Reason: To ensure that the plans are suitable for construction purposes.

34. Energy Australia requirements

Prior to issue of the Construction Certificate, the applicant must contact Energy Australia regarding power supply for the subject development. A written response detailing the full requirements of Energy Australia (including any need for underground cabling, substations or similar within or in the vicinity the development) shall be submitted to the Principal Certifying Authority for approval prior to issue of the Construction Certificate.

Any structures or other requirements of Energy Australia shall be indicated on the plans issued with the Construction Certificate, to the satisfaction of the Principal Certifying Authority and Energy Australia. The requirements of Energy Australia must be met in full prior to issue of the Occupation Certificate.

Reason: To ensure compliance with the requirements of Energy Australia.

35. Utility provider requirements

Prior to issue of the Construction Certificate, the applicant must make contact with all relevant utility providers whose services will be impacted upon by the development. A written copy of the requirements of each provider, as determined necessary by the Certifying Authority, must be obtained. All utility services or appropriate conduits for the same must be provided by the developer in accordance with the specifications of the utility providers.

Reason: To ensure compliance with the requirements of relevant utility providers.

36. Underground services

All electrical services (existing and proposed) shall be undergrounded from the proposed building on the site to the appropriate power pole(s) or other connection point. Undergrounding of services must not disturb the root system of existing trees and shall be undertaken in accordance with the requirements of the relevant service provider. Documentary evidence that the relevant service provider has been consulted and that their requirements have been met are to be provided to the Certifying Authority prior to the issue of the Construction Certificate. All electrical and telephone services to the subject property must be placed underground and any redundant poles are to be removed at the expense of the applicant.

Reason: To provide infrastructure that facilitates the future improvement of the streetscape by relocation of overhead lines below ground.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE OR PRIOR TO DEMOLITION, EXCAVATION OR CONSTRUCTION (WHICHEVER COMES FIRST):

37. Infrastructure restorations fee

To ensure that damage to Council Property as a result of construction activity is rectified in a timely matter:

- a) All work or activity taken in furtherance of the development the subject of this approval must be undertaken in a manner to avoid damage to Council Property and must not jeopardise the safety of any person using or occupying the adjacent public areas.
- b) The applicant, builder, developer or any person acting in reliance on this approval shall be responsible for making good any damage to Council Property, and for the removal from Council Property of any waste bin, building materials, sediment, silt, or any other material or article.
- c) The Infrastructure Restoration Fee must be paid to the Council by the applicant prior to both the issue of the Construction Certificate and the commencement of any earthworks or construction.
- d) In consideration of payment of the Infrastructure Restorations Fee, Council will undertake such inspections of Council Property as Council considers necessary and also undertake, on behalf of the applicant, such restoration work to Council

Property, if any, that Council considers necessary as a consequence of the development. The provision of such restoration work by the Council does not absolve any person of the responsibilities contained in (a) to (b) above. Restoration work to be undertaken by the Council referred to in this condition is limited to work that can be undertaken by Council at a cost of not more than the Infrastructure Restorations Fee payable pursuant to this condition.

e) In this condition:

“Council Property” includes any road, footway, footpath paving, kerbing, guttering, crossings, street furniture, seats, letter bins, trees, shrubs, lawns, mounds, bushland, and similar structures or features on any road or public road within the meaning of the Local Government Act 1993 (NSW) or any public place; and

“Infrastructure Restoration Fee” means the Infrastructure Restorations Fee calculated in accordance with the Schedule of Fees & Charges adopted by Council as at the date of payment and the cost of any inspections required by the Council of Council Property associated with this condition.

Reason: To maintain public infrastructure.

38. Section 94 contribution – residential development

A contribution pursuant to section 94 of the Environmental Planning and Assessment Act as specified in Ku-ring-gai Section 94 Contributions Plan 2004-2009 for the services detailed in column A and for the amount detailed in Column B is required.

Column A	Column B
Community facilities	\$52,037.01
Park acquisition and embellishment works	\$842,488.97
Park embellishment works	\$99,983.28
Sports grounds works	\$177,591.35
Aquatic / leisure centres	\$10,513.37
Traffic and transport	\$14,832.60
Section 94 Plan administration	\$13,296.67
Total contribution is:	\$1,210,743.23

The contribution shall be paid to Council prior to the commencement of any development (including demolition) or prior to the issue of the Construction Certificate (whichever comes first). The charges may vary at the time of payment in accordance with Council’s Section 94 Contributions Plan to reflect changes in land values, construction costs and the consumer price index. Prior to payment, you are advised to check the contribution amount required with Council.

Reason: To ensure the provision, extension or augmentation of community facilities, recreation facilities, open space and administration that will, or are likely to be, required as a consequence of the development.

CONDITIONS TO BE SATISFIED DURING THE DEMOLITION, EXCAVATION AND CONSTRUCTION PHASES:

39. Approved plans to be on site

A copy of all approved and certified plans, specifications and documents incorporating conditions of consent and certification (including the Construction Certificate if required for the work) shall be kept on site at all times during the demolition, excavation and construction phases and must be readily available to any officer of Council or the Principal Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

40. Engineering fees

For the purpose of any development related inspections by Ku-ring-gai Council engineers, the corresponding fees set out in Councils adopted *Schedule of Fees and Charges* are payable to Council. A re-inspection fee per visit may be charged where work is unprepared at the requested time of inspection, or where remedial work is unsatisfactory and a further inspection is required. Engineering fees must be paid in full prior to any final consent from Council.

Reason: To protect public infrastructure.

41. Prescribed conditions

The applicant shall comply with any relevant prescribed conditions of development consent under clause 98 of the Environmental Planning and Assessment Regulation. For the purposes of section 80A (11) of the Environmental Planning and Assessment Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- The work must be carried out in accordance with the requirements of the Building Code of Australia
- In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any works commence.

Reason: Statutory requirement.

42. Statement of compliance with Australian Standards

The demolition work shall comply with the provisions of Australian Standard AS2601: 2001 The Demolition of Structures. The work plans required by AS2601: 2001 shall be accompanied by a written statement from a suitably qualified person that the proposal contained in the work plan comply with the safety requirements of the Standard. The work plan and the statement of compliance shall be submitted to the satisfaction of the Principal Certifying Authority prior to the commencement of any works.

Reason: To ensure compliance with the Australian Standards.

43. Demolition, excavation and construction work hours

Demolition, excavation, construction work and deliveries of building material and equipment must not take place outside the hours of 7.00am to 5.00pm Monday to Friday and 8.00am to 12.00pm Saturday. No work and no deliveries are to take place on Sundays and public holidays.

Excavation or removal of any materials using machinery of any kind, including compressors and jack hammers, must be limited to between 7.30am and 5.00pm Monday to Friday, with a respite break of 45 minutes between 12 noon and 1.00pm.

Where it is necessary for works to occur outside of these hours (i.e. concrete pours and standing of plant), approval for such will be subject to the issue of an "outside of hours works permit" from Council as well as notification of the surrounding properties likely to be affected by the proposed works.

Note: Failure to obtain a permit for work outside of the approved hours will result in on the spot fines being issued.

Reason: To ensure reasonable standards of amenity for occupants of neighbouring properties.

44. Construction noise

During excavation, demolition and construction phases, noise generated from the site shall be controlled in accordance with the recommendations of the approved noise and vibration management plan.

Reason: To ensure reasonable standards of amenity to neighbouring properties.

45. Site notice

A site notice shall be erected on the site prior to any work commencing and shall be displayed throughout the works period.

The site notice must:

- be prominently displayed at the boundaries of the site for the purposes of informing the public that unauthorised entry to the site is not permitted
- display project details including, but not limited to the details of the builder, Principal Certifying Authority and structural engineer
- be durable and weatherproof
- display the approved hours of work, the name of the site/project manager, the responsible managing company (if any), its address and 24 hour contact phone number for any inquiries, including construction/noise complaint are to be displayed on the site notice
- be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted

Reason: To ensure public safety and public information.

46. Dust control

During excavation, demolition and construction, adequate measures shall be taken to prevent dust from affecting the amenity of the neighbourhood. The following measures must be adopted:

- physical barriers shall be erected at right angles to the prevailing wind direction or shall be placed around or over dust sources to prevent wind or activity from generating dust
- earthworks and scheduling activities shall be managed to coincide with the next stage of development to minimise the amount of time the site is left cut or exposed
- all materials shall be stored or stockpiled at the best locations
- the ground surface should be dampened slightly to prevent dust from becoming airborne but should not be wet to the extent that run-off occurs
- all vehicles carrying spoil or rubble to or from the site shall at all times be covered to prevent the escape of dust
- all equipment wheels shall be washed before exiting the site using manual or automated sprayers and drive-through washing bays
- gates shall be closed between vehicle movements and shall be fitted with shade cloth
- cleaning of footpaths and roadways shall be carried out daily

Reason: To protect the environment and amenity of surrounding properties.

47. Post-construction dilapidation report

The applicant shall engage a suitably qualified person to prepare a post construction dilapidation report at the completion of the construction works. This report is to ascertain whether the construction works created any structural damage to adjoining buildings, infrastructure and roads. The report is to be submitted to the Principal Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings, infrastructure and roads, the Principal Certifying Authority must:

- compare the post-construction dilapidation report with the pre-construction dilapidation report
- have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.

A copy of this report is to be forwarded to Council at the completion of the construction works.

Reason: Management of records.

48. Further geotechnical input

The geotechnical and hydro-geological works implementation, inspection, testing and monitoring program for the excavation and construction works must be in accordance with the report by Jeffery and Katauskas. Over the course of the works, a qualified geotechnical/hydro-geological engineer must complete the following:

- further geotechnical investigations and testing recommended in the above report(s) and as determined necessary
- further monitoring and inspection at the hold points recommended in the above report(s) and as determined necessary
- written report(s) including certification(s) of the geotechnical inspection, testing and monitoring programs

Reason: To ensure the safety and protection of property.

49. Compliance with submitted geotechnical report

A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee excavation.

Geotechnical aspects of the development work, namely:

- appropriate excavation method and vibration control
- support and retention of excavated faces
- hydro-geological considerations

must be undertaken in accordance with the recommendations of the geotechnical report prepared by Jeffery and Katauskas. Approval must be obtained from all affected property owners, including Ku-ring-gai Council, where rock anchors (both temporary and permanent) are proposed below adjoining property(ies).

Reason: To ensure the safety and protection of property.

50. Use of road or footpath

During excavation, demolition and construction phases, no building materials, plant or the like are to be stored on the road or footpath without written approval being obtained from Council beforehand. The pathway shall be kept in a clean, tidy and safe condition during building operations. Council reserves the right, without notice, to rectify any such breach and to charge the cost against the applicant/owner/builder, as the case may be.

Reason: To ensure safety and amenity of the area.

51. Guarding excavations

All excavation, demolition and construction works shall be properly guarded and protected with hoardings or fencing to prevent them from being dangerous to life and property.

Reason: To ensure public safety.

52. Toilet facilities

During excavation, demolition and construction phases, toilet facilities are to be provided, on the work site, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Reason: Statutory requirement.

53. Protection of public places

If the work involved in the erection, demolition or construction of the development is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient, or building involves the enclosure of a public place, a hoarding or fence must be erected between the work site and the public place.

If necessary, a hoarding is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

Any hoarding, fence or awning is to be removed when the work has been completed.

Reason: To protect public places.

54. Recycling of building material (general)

During demolition and construction, the Principal Certifying Authority shall be satisfied that building materials suitable for recycling have been forwarded to an appropriate registered business dealing in recycling of materials. Materials to be recycled must be kept in good order.

Reason: To facilitate recycling of materials.

55. Approval for rock anchors

Approval is to be obtained from the property owner for any anchors proposed beneath adjoining private property. If such approval cannot be obtained, then the excavated faces are to be shored or propped in accordance with the recommendations of the geotechnical and structural engineers.

Reason: To ensure the ongoing safety and protection of property.

56. Maintenance period for works in public road

A maintenance period of six (6) months applies to all public infrastructure work carried out by the applicant - after the works have been completed to the satisfaction of Ku-ring-gai Council. In that maintenance period, the applicant shall be liable for any section of the public infrastructure work which fails to perform in the designed manner, or as would reasonably be expected under the operating conditions. The maintenance period shall commence once the applicant receives a formal letter from Council stating that the works involving public infrastructure have been completed satisfactorily.

Reason: To protect public infrastructure.

57. Road reserve safety

All public footways and roadways fronting and adjacent to the site must be

maintained in a safe condition at all times during the course of the development works. Construction materials must not be stored in the road reserve. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site. Where public infrastructure is damaged, repair works must be carried out when and as directed by Council officers. Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects, Council may undertake proceedings to stop work.

Reason: To ensure safe public footways and roadways during construction.

58. Road repairs necessitated by excavation and construction works

It is highly likely that damage will be caused to the roadway at or near the subject site as a result of the construction (or demolition or excavation) works. The applicant, owner and builder (and demolition or excavation contractor as appropriate) will be held responsible for repair of such damage, regardless of the Infrastructure Restorations Fee paid (this fee is to cover wear and tear on Council's wider road network due to heavy vehicle traffic, not actual major damage).

Section 102(1) of the Roads Act states "A person who causes damage to a public road is liable to pay to the appropriate roads authority the cost incurred by that authority in making good the damage."

Council will notify when road repairs are needed, and if they are not carried out within 48 hours, then Council will proceed with the repairs, and will invoice the applicant, owner and relevant contractor for the balance.

Reason: To protect public infrastructure.

59. Services

Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the applicant and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the applicants full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services (including water, phone, gas and the like). Council accepts no responsibility for any matter arising from its approval to this application involving any influence upon utility services provided by another authority.

Reason: Provision of utility services.

60. Temporary rock anchors

If the use of temporary rock anchors extending into the road reserve is proposed, then approval must be obtained from Council and/or the Roads and Traffic Authority in accordance with Section 138 of the Roads Act 1993. The Applicant is to submit details of all the work that is to be considered, and the works are not to commence until approval has been granted. The designs are to include details of the following:

- How the temporary rock anchors will be left in a way that they will not harm or interfere with any future excavation in the public road
- That the locations of the rock anchors are registered with Dial Before You Dig
- That approval of all utility authorities likely to use the public road has been obtained. All temporary rock anchors are located outside the allocations for the various utilities as adopted by the Streets Opening Conference.
- That any remaining de-stressed rock anchors are sufficiently isolated from the structure that they cannot damage the structure if pulled during future excavations or work in the public road.
- That signs will be placed and maintained on the building stating that de-stressed rock anchors remain in the public road and include a contact number for the building manager. The signs are to be at least 600mm x 450mm with lettering on the signs is to be no less than 75mm high. The signs are to be at not more than 60m spacing. At least one sign must be visible from all locations on the footpath outside the property. The wording on the signs is to be submitted to Council's Director Technical Services for approval before any signs are installed.

Permanent rock anchors are not to be used where any part of the anchor extends outside the development site into public areas or road reserves.

All works in the public road are to be carried out in accordance with the Conditions of Construction issued with any approval of works granted under Section 138 of the Roads Act 1993.

Reason: To ensure the ongoing safety and protection of property.

61. Temporary disposal of stormwater runoff

During construction, stormwater runoff must be disposed of in a controlled manner that is compatible with the erosion and sediment controls on the site. Immediately upon completion of any impervious areas on the site (including roofs, driveways, paving) and where the final drainage system is incomplete, the necessary temporary drainage systems must be installed to manage and control runoff as far as the approved point of stormwater discharge. Such measures shall be to the satisfaction of the Principal Certifying Authority.

Reason: To preserve and enhance the natural environment.

62. Drainage to interallotment easement

Stormwater runoff from all new impervious areas and subsoil drainage systems shall be piped and connected to the interallotment stormwater drainage line benefiting the site. The interallotment line must be covered by the necessary easement for drainage which may exist or need to be created under this consent.

Reason: To protect the environment.

63. Grated drain at garage

A 200mm wide grated channel/trench drain, with a heavy-duty removable galvanised grate is to be provided in front of the garage door/basement parking slab to collect

driveway runoff. The channel drain shall be connected to the main drainage system and must have an outlet of minimum diameter 150mm to prevent blockage by silt and debris.

Reason: Stormwater control.

64. Sydney Water Section 73 Compliance Certificate

The applicant must obtain a **Section 73 Compliance Certificate** under the *Sydney Water Act 1994*. An application must be made through an authorised Water Servicing Co-ordinator. The applicant is to refer to "Your Business" section of Sydney Water's web site at www.sydneywater.com.au then the "e-develop" icon or telephone 13 20 92. Following application a "Notice of Requirements" will detail water and sewer extensions to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Reason: Statutory requirement.

65. Arborist's report

The trees to be retained shall be inspected, monitored and treated by a qualified arborist during and after completion of development works to ensure their long term survival. Regular inspections and documentation from the arborist to the Principal Certifying Authority are required at the following times or phases of work:

Schedule

Tree/location

All existing trees to be retained on site and within 6.0m of proposed works of trees located on adjoining properties

Time of inspection

Immediately prior to the start of any works on site.
Completion of demolition works.
Completion of regrading of site.
At four monthly intervals during construction period.
Completion of all external construction works.
Completion of all works on site.

Reason: To ensure protection of existing trees.

66. Canopy/root pruning

Canopy and/or root pruning of the following tree(s) which is necessary to accommodate the approved building works shall be undertaken by an experienced arborist/horticulturist, with a minimum qualification of the horticulture certificate or tree surgery certificate:

Schedule

Tree/location

#10 *Ulmus parvifolia* (Chinese Elm)
Adjacent to northern site boundary

Tree works

Root pruning on southern side

Reason: To protect the environment.

67. Treatment of tree roots

If tree roots are required to be severed for the purposes of constructing the approved works, they shall be cut cleanly by hand, by an experienced arborist/horticulturist with a minimum qualification of horticulture certificate or tree surgery certificate

Reason: To protect existing trees.

68. Cutting of tree roots

No tree roots of 30mm or greater in diameter located within the specified radius of the trunk(s) of the following, tree(s) shall be severed or injured in the process of any works during the construction period.

Schedule Tree/location	Radius from trunk
#1 <i>Arecastrum romanzoffianum</i> (Cocco Palm) Adjacent to eastern/Culworth Ave site boundary	3.0m
#2 <i>Magnolia soulangeana</i> (Saucer Magnolia) Adjacent to eastern/Culworth Ave site boundary	3.0m
#3 <i>Nyssa sylvatica</i> (Tupelo) Adjacent to eastern/Culworth Ave site boundary	5.0m
#10 <i>Ulmus parvifolia</i> (Chinese Elm) Adjacent to northern site boundary	4.5m
#15 <i>Metasequoia glyptostroboides</i> (Dawn Redwood) Adjacent to southern site boundary in neighbouring property	6.0m
#22 <i>Euphorbia tirucalli</i> (Pencil Tree) Adjacent to western site boundary	3.0m
#26 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#27 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#28 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#30 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	3.0m
#31 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	3.0m
#32 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to eastern site boundary	3.0m
#33 <i>Howea forsteriana</i> (Kentia Palm) Adjacent to eastern site boundary	2.0m
#34 <i>Pittosporum undulatum</i> (Sweet Pittosporum) Adjacent to northern site boundary	4.0m
#35 <i>Syzygium luehmannii</i> (Lillypilly) Adjacent to northern site boundary	5.0m
#37 <i>Camellia japonica</i> (Japanese Camellia) Adjacent to western site boundary	4.0m
#38 <i>Fraxinus griffithii</i> (Flowering Ash) Adjacent to western site boundary in neighbouring property	4.0m
#39 <i>Fraxinus griffithii</i> (Flowering Ash) Adjacent to western site boundary in neighbouring property	4.0m
#41 <i>Liquidambar styraciflua</i> (Sweet Gum) Adjacent to northern site boundary	6.0m
#44 <i>Ulmus spp.</i> (Elm)	4.0m

Schedule**Tree/location****Radius from trunk**

Adjacent to northern site boundary #46 <i>Camellia japonica</i> (Japanese Camellia)	3.0m
Adjacent to western site boundary #47 <i>Eucalyptus saligna</i> (Sydney Bluegum)	11.0m
Adjacent to northeast site corner in neighbouring property #48 <i>Eucalyptus acmeniodes</i> (White Mahogany)	4.0m
Adjacent to northern site boundary in neighbouring property #49 <i>Stenocarpus sinuatus</i> (Q'ld Firewheel Tree)	3.0m
Adjacent to eastern site boundary #50 <i>Jacaranda mimosifolia</i> (Jacaranda)	4.0m
Adjacent to eastern site boundary #54 <i>Jacaranda mimosifolia</i> (Jacaranda)	4.0m
Adjacent to northern site boundary in neighbouring property #55 <i>Acer palmatum</i> (Japanese Maple)	4.0m
Adjacent to northern site boundary in neighbouring property <i>Camellia sasanqua</i> hedge	2.0m
Adjacent to southern site boundary	

Reason: To protect existing trees.

69. Approved tree works

Approval is given for the following works to be undertaken to trees on the site:

Schedule**Tree location****Approved tree works**

#4 <i>Malus floribunda</i> (Crabapple)	Removal
Adjacent to eastern/Culworth Ave site boundary #5 <i>Camellia sasanqua</i> (Chinese Camellia)	Removal
Adjacent to eastern/Culworth Ave site boundary #6 <i>Cupressocyparis leylandii</i> (Leighton's Green)	Removal
Adjacent to eastern/Culworth Ave site boundary #7 <i>Acer palmatum</i> (Japanese Maple)	Removal
Adjacent to eastern/Culworth Ave site boundary #8 <i>Cupressocyparis leylandii</i> (Leighton's Green)	Removal
Adjacent to eastern/Culworth Ave site boundary #9 <i>Acer palmatum</i> (Japanese Maple)	Removal
Adjacent to eastern/Culworth Ave site boundary #10a <i>Lagerstroemia indica</i> (Crepe Myrtle)	Removal
Adjacent to northern site boundary #11 <i>Nyssa sylvatica</i> (Tupelo)	Removal
Adjacent to northern site boundary #12 <i>Betula pendula</i> (Silver Birch)	Removal
Within building A footprint #13 <i>Betula pendula</i> (Silver Birch)	Removal
Within Building A footprint #14 <i>Ginkgo biloba</i> (Maidenhair tree)	Removal
Within Building A footprint #16 <i>Pyrus ussuriensis</i> (Manchurian Pear)	Removal
Within Building B footprint #17 <i>Jacaranda mimosifolia</i> (Jacaranda)	Removal
Within building B footprint	

Schedule**Tree location****Approved tree works**

#18 <i>Prunus serrulata</i> (Weeping Cherry) Centrally located on site	Removal
#19 <i>Chamaecyparis obtusa</i> 'Crippsii' Centrally located on site	Removal
#20 <i>Ulmus parvifolia</i> (Chinese elm) Adjacent to western site boundary	Removal
#21 <i>Eucalyptus saligna</i> (Sydney Bluegum) Adjacent to western site boundary	Removal
#23 <i>Phoenix canariensis</i> (Canary Island Date Palm) Adjacent to western site boundary	Removal
#24 <i>Olea europaea var. africana</i> (African Olive) Adjacent to western site boundary	Removal
#29 <i>Eucalyptus acmenoides</i> (White Mahogany) Adjacent to southwest site corner	Removal
#36 <i>Magnolia soulangeana</i> (Saucer Magnolia) Adjacent to northern site boundary	Removal
#40 <i>Ulmus parvifolia</i> (Chinese Elm) Adjacent to northern site boundary	Removal
#42 <i>Cordyline australis</i> (Cabbage Tree) Adjacent to northern site boundary	Removal
#43 <i>Cordyline australis</i> (Cabbage Tree) Adjacent to northern site boundary	Removal
#45 <i>Jacaranda mimosifolia</i> (Jacaranda) Adjacent to northern site boundary in adjoining property	Removal
#51 <i>Prunus serrulata</i> (Weeping Cherry) Centrally located on site	Removal
#52 <i>Camellia sasanqua</i> (Chinese Camellia) Centrally located on site	Removal
#53 <i>Camellia japonica</i> (Japanese camellia) Centrally located on site	Removal

Removal or pruning of any other tree on the site is not approved.

Reason: To ensure that the development is in accordance with the determination.

70. Excavation near trees

No mechanical excavation shall be undertaken within the specified radius of the trunk(s) of the following tree(s) until root pruning by hand along the perimeter line of such works is completed:

Schedule**Tree/location****Radius from trunk**

#10 <i>Ulmus parvifolia</i> (Chinese Elm) Adjacent to northern site boundary	6.0m
---	------

Reason: To protect existing trees.

71. Hand excavation

All excavation within the specified radius of the trunk(s) of the following tree(s) shall be hand dug:

Schedule

Tree/location

Radius from trunk

#1 <i>Arecastrum romanzoffianum</i> (Cocco Palm)	3.0m
Adjacent to eastern/Culworth Ave site boundary	
#2 <i>Magnolia soulangeana</i> (Saucer Magnolia)	3.0m
Adjacent to eastern/Culworth Ave site boundary	
#3 <i>Nyssa sylvatica</i> (Tupelo)	5.0m
Adjacent to eastern/Culworth Ave site boundary	
#10 <i>Ulmus parvifolia</i> (Chinese Elm)	4.5m
Adjacent to northern site boundary	
#15 <i>Metasequoia glyptostroboides</i> (Dawn Redwood)	6.0m
Adjacent to southern site boundary in neighbouring property	
#22 <i>Euphorbia tirucalli</i> (Pencil Tree)	3.0m
Adjacent to western site boundary	
#26 <i>Eucalyptus acmeniodes</i> (White Mahogany)	5.0m
Adjacent to western site boundary	
#27 <i>Eucalyptus acmeniodes</i> (White Mahogany)	5.0m
Adjacent to western site boundary	
#28 <i>Eucalyptus acmeniodes</i> (White Mahogany)	5.0m
Adjacent to western site boundary	
#30 <i>Camellia japonica</i> (Japanese Camellia)	3.0m
Adjacent to eastern site boundary	
#31 <i>Camellia japonica</i> (Japanese Camellia)	3.0m
Adjacent to eastern site boundary	
#32 <i>Camellia japonica</i> (Japanese Camellia)	3.0m
Adjacent to eastern site boundary	
#33 <i>Howea forsteriana</i> (Kentia Palm)	2.0m
Adjacent to eastern site boundary	
#34 <i>Pittosporum undulatum</i> (Sweet Pittosporum)	4.0m
Adjacent to northern site boundary	
#35 <i>Syzigium luehmannii</i> (Lillypilly)	5.0m
Adjacent to northern site boundary	
#37 <i>Camellia japonica</i> (Japanese Camellia)	4.0m
Adjacent to western site boundary	
#38 <i>Fraxinus griffithii</i> (Flowering Ash)	4.0m
Adjacent to western site boundary in neighbouring property	
#39 <i>Fraxinus griffithii</i> (Flowering Ash)	4.0m
Adjacent to western site boundary in neighbouring property	
#41 <i>Liquidambar styraciflua</i> (Sweet Gum)	6.0m
Adjacent to northern site boundary	
#44 <i>Ulmus spp.</i> (Elm)	4.0m
Adjacent to northern site boundary	
#46 <i>Camellia japonica</i> (Japanese Camellia)	3.0m
Adjacent to western site boundary	
#47 <i>Eucalyptus saligna</i> (Sydney Bluegum)	11.0m
Adjacent to northeast site corner in neighbouring property	
#48 <i>Eucalyptus acmeniodes</i> (White Mahogany)	4.0m
Adjacent to northern site boundary in neighbouring property	
#49 <i>Stenocarpus sinuatus</i> (Q'ld Firewheel Tree)	3.0m
Adjacent to eastern site boundary	
#50 <i>Jacaranda mimosifolia</i> (Jacaranda)	4.0m
Adjacent to eastern site boundary	
#54 <i>Jacaranda mimosifolia</i> (Jacaranda)	4.0m
Adjacent to northern site boundary in neighbouring property	
#55 <i>Acer palmatum</i> (Japanese Maple)	4.0m
Adjacent to northern site boundary in neighbouring property	
<i>Camellia sasanqua</i> hedge	2.0m
Adjacent to southern site boundary	

Reason: To protect existing trees.

72. Thrust boring

Excavation for the installation of any services within the specified radius of the trunk(s) of the following tree(s) shall utilise the thrust boring method. Thrust boring shall be carried out at least 600mm beneath natural ground level to minimise damage to tree(s) root system

Schedule Tree/location	Radius from trunk
#3 <i>Nyssa sylvatica</i> (Tupelo) Adjacent to eastern/Culworth Ave site boundary	5.0m
#10 <i>Ulmus parvifolia</i> (Chinese Elm) Adjacent to northern site boundary	4.5m
#15 <i>Metasequoia glyptostroboides</i> (Dawn Redwood) Adjacent to southern site boundary in neighbouring property	6.0m
#26 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#27 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#28 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to western site boundary	5.0m
#34 <i>Pittosporum undulatum</i> (Sweet Pittosporum) Adjacent to northern site boundary	4.0m
#35 <i>Syzygium luehmannii</i> (Lillypilly) Adjacent to northern site boundary	5.0m
#38 <i>Fraxinus griffithii</i> (Flowering Ash) Adjacent to western site boundary in neighbouring property	4.0m
#39 <i>Fraxinus griffithii</i> (Flowering Ash) Adjacent to western site boundary in neighbouring property	4.0m
#41 <i>Liquidambar styraciflua</i> (Sweet Gum) Adjacent to northern site boundary	6.0m
#44 <i>Ulmus spp.</i> (Elm) Adjacent to northern site boundary	4.0m
#47 <i>Eucalyptus saligna</i> (Sydney Bluegum) Adjacent to northeast site corner in neighbouring property	11.0m
#48 <i>Eucalyptus acmeniodes</i> (White Mahogany) Adjacent to northern site boundary in neighbouring property	4.0m
#49 <i>Stenocarpus sinuatus</i> (Q'ld Firewheel Tree) Adjacent to eastern site boundary	3.0m
#50 <i>Jacaranda mimosifolia</i> (Jacaranda) Adjacent to eastern site boundary	4.0m
#54 <i>Jacaranda mimosifolia</i> (Jacaranda) Adjacent to northern site boundary in neighbouring property	4.0m
#55 <i>Acer palmatum</i> (Japanese Maple) Adjacent to northern site boundary in neighbouring property	4.0m
<i>Camellia sasanqua</i> hedge Adjacent to southern site boundary	2.0m
All existing trees Selkirk Park	Beneath canopy drip line

Reason: To protect existing trees.

73. No storage of materials beneath trees

No activities, storage or disposal of materials shall take place beneath the canopy of any tree protected under Council's Tree Preservation Order at any time.

Reason: To protect existing trees.

74. Removal of refuse

All builders' refuse, spoil and/or material unsuitable for use in landscape areas shall be removed from the site on completion of the building works.

Reason: To protect the environment.

75. Canopy replenishment trees to be planted

The canopy replenishment trees to be planted shall be maintained in a healthy and vigorous condition until they attain a height of 5.0 metres whereby they will be protected by Council's Tree Preservation Order. Any of the trees found faulty, damaged, dying or dead shall be replaced with the same species

Reason: To maintain the treed character of the area.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE:

76. Easement for waste collection

Prior to issue of the Occupation Certificate, an easement for waste collection is to be created under Section 88B of the Conveyancing Act 1919. This is to permit legal access for Council, Council's contractors and their vehicles over the subject property for the purpose of collecting waste from the property. The terms of the easement are to be generally in accordance with Council's draft terms for an easement for waste collection and shall be to the satisfaction of Council's Development Engineer.

Reason: To permit legal access for Council, Council's contractors and their vehicles over the subject site for waste collection.

77. Compliance with BASIX Certificate

Prior to the issue of an Occupation Certificate, the Principal Certifying Authority shall be satisfied that all commitments listed in BASIX Certificate No. 205913M have been complied with.

Reason: Statutory requirement.

78. Completion of landscape works

Prior to the release of the Occupation Certificate, the Principal Certifying Authority is to be satisfied that all landscape works, including the removal of all noxious and/or environmental weed species, have been undertaken in accordance with the approved plan(s) and conditions of consent.

Reason: To ensure that the landscape works are consistent with the development consent.

79. Retention and re-use positive covenant

Prior to issue of the Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the property with the requirement to maintain the site stormwater retention and re-use facilities on the property.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instruments for protection of retention and re-use facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Water Management Development Control Plan No. 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the reuse and retention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents showing the covenants and restrictions must be submitted to and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

80. Provision of copy of OSD designs if Council is not the PCA

Prior to issue of the Occupation Certificate, the following must be provided to Council's Development Engineer:

- a copy of the approved Construction Certificate stormwater detention/retention design for the site
- A copy of any works-as-executed drawings required by this consent
- The Engineer's certification of the as-built system.

Reason: For Council to maintain its database of as-constructed on-site stormwater detention systems.

81. Certification of drainage works (dual occupancies and above)

Prior to issue of the Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the stormwater drainage works have been satisfactorily completed in accordance with the approved Construction Certificate drainage plans
- the minimum retention and on-site detention storage volume requirements of BASIX and Ku-ring-gai Water Management Development Control Plan No. 47 respectively, have been achieved
- retained water is connected and available for use
- basement and subsoil areas are able to drain via a pump/sump system installed in accordance with AS3500.3 and Appendix 7.1.1 of Ku-ring-gai Water Management Development Control Plan No. 47
- all grates potentially accessible by children are secured

- components of the new drainage system have been installed by a licensed plumbing contractor in accordance with the Plumbing and Drainage Code AS3500.3 2003 and the Building Code of Australia
- all enclosed floor areas, including habitable and garage floor levels, are safeguarded from outside stormwater runoff ingress by suitable differences in finished levels, gradings and provision of stormwater collection devices

The rainwater certification sheet contained in Appendix 13 of the Ku-ring-gai Water Management Development Control Plan No. 47, must be completed and attached to the certification. Where an on-site detention system has been constructed, the on-site detention certification sheet contained in Appendix 4 of DCP 47 must also be completed and attached to the certification.

Note: Evidence from a qualified and experienced consulting civil/hydraulic engineer documenting compliance with the above is to be provided to Council prior to the issue of an Occupation Certificate.

Reason: To protect the environment.

82. WAE plans for stormwater management and disposal (dual occupancy and above)

Prior to issue of the Occupation Certificate, a registered surveyor must provide a works as executed survey of the completed stormwater drainage and management systems. The survey must be submitted to and approved by the Principal Certifying Authority prior to issue of the Occupation Certificate. The survey must indicate:

- as built (reduced) surface and invert levels for all drainage pits
- gradients of drainage lines, materials and dimensions
- as built (reduced) level(s) at the approved point of discharge to the public drainage system
- as built location and internal dimensions of all detention and retention structures on the property (in plan view) and horizontal distances to nearest adjacent boundaries and structures on site
- the achieved storage volumes of the installed retention and detention storages and derivative calculations
- as built locations of all access pits and grates in the detention and retention system(s), including dimensions
- the size of the orifice or control fitted to any on-site detention system
- dimensions of the discharge control pit and access grates
- the maximum depth of storage possible over the outlet control
- top water levels of storage areas and indicative RL's through the overland flow path in the event of blockage of the on-site detention system

The works as executed plan(s) must show the as built details above in comparison to those shown on the drainage plans approved with the Construction Certificate prior to commencement of works. All relevant levels and details indicated must be marked in red on a copy of the Principal Certifying Authority stamped construction certificate stormwater plans.

Reason: To protect the environment.

83. Basement pump-out maintenance

Prior to issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that a maintenance regime has been prepared for the basement stormwater pump-out system.

Note: A maintenance regime specifying that the system is to be regularly inspected and checked by qualified practitioners is to be prepared by a suitable qualified professional and provided to the Principal Certifying Authority.

Reason: To protect the environment.

84. OSD positive covenant/restriction

Prior to issue of the Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the owner with the requirement to maintain the on-site stormwater detention facilities on the lot.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instrument for protection of on-site detention facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Council Water Management DCP 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the on-site detention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents, showing the covenants and restrictions, must be submitted and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

85. Easement drainage line construction

Prior to issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that the required interallotment drainage system has been installed and surveyed under the supervision of a designing engineer or equivalent professional.

Note: At the completion of the interallotment works, the following must be submitted to the Principal Certifying Authority for approval:

- details from the supervising engineer that the as-constructed works comply with the approved interallotment design documentation
- a full works as executed drawing of the as built interallotment drainage line (dimensions, grades, materials, invert levels) prepared by a registered surveyor, and details from the surveyor that all drainage structures are wholly contained within existing drainage easement(s)

Reason: To protect the environment.

86. Sydney Water Section 73 Compliance Certificate

Prior to issue of an Occupation Certificate the Section 73 Sydney water Compliance Certificate must be obtained and submitted to the Principal Certifying Authority

Reason: Statutory requirement.

87. Certification of as-constructed driveway/car park – RFB

Prior to issue of an Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the as-constructed car park complies with the approved Construction Certificate plans
- the completed vehicle access and accommodation arrangements comply with Australian Standard 2890.1 – 2004 “Off-Street car parking” in terms of minimum parking space dimensions
- finished driveway gradients and transitions will not result in the scraping of the underside of cars
- no doors, gates, grilles or other structures have been provided in the access driveways to the basement car park, which would prevent unrestricted access for internal garbage collection from the basement garbage storage and collection area
- the vehicular headroom requirements of:
 - Australian Standard 2890.1 – “Off-street car parking”,
 - **2.44 metres height clearance** for waste collection trucks (refer DCP 40) are met from the public street into and within the applicable areas of the basement car park.

Note: Evidence from a suitably qualified and experienced traffic/civil engineer indicating compliance with the above is to be provided to and approved by the Principal Certifying Authority prior to the issue of an Occupation Certificate.

Reason: To ensure that vehicular access and accommodation areas are compliant with the consent.

88. Reinstatement of redundant crossings and completion of infrastructure works

Prior to issue of the Occupation Certificate, the Principal Certifying Authority must be satisfied that the following works in the road reserve have been completed:

- new concrete driveway crossing in accordance with levels and specifications issued by Council
- removal of all redundant driveway crossings and kerb laybacks (or sections thereof) and reinstatement of these areas to footpath, turfed verge and upright kerb and gutter (reinstatement works to match surrounding adjacent infrastructure with respect to integration of levels and materials)
- full repair and resealing of any road surface damaged during construction
- full replacement of damaged sections of grass verge with a non-friable turf of

native variety to match existing

All works must be completed in accordance with the General Specification for the Construction of Road and Drainage Works in Ku-ring-gai Council, dated November 2004. The Occupation Certificate must not be issued until all damaged public infrastructure caused as a result of construction works on the subject site (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub contractors, concrete vehicles) is fully repaired to the satisfaction of Council. Repair works shall be at no cost to Council.

Reason: To protect the streetscape.

89. Construction of works in public road – approved plans

Prior to issue of the Occupation Certificate, the Principal Certifying Authority must be satisfied that all approved road, footpath and/or drainage works have been completed in the road reserve in accordance with the Council approval and accompanying drawings, conditions and specifications.

The works must be supervised by the applicant's designing engineer and completed and approved to the satisfaction of Ku-ring-gai Council.

The supervising consulting engineer is to provide certification upon completion that the works were constructed in accordance with the Council approved stamped drawings. The works must be subject to inspections by Council at the hold points noted on the approval. All conditions attached to the approved drawings for these works must be met prior to the Occupation Certificate being issued.

Reason: To ensure that works undertaken on Council's infrastructure are to the satisfaction of Council.

CONDITIONS TO BE SATISFIED AT ALL TIMES:

90. Visual privacy

The living room windows to Units, A1-10, A2-15 and A3-20 and the dining room window of Unit AG - 05 to the western elevation of Building A are to be fitted with movable privacy screens being of a shutter type with dimensions 2m x 2m.

Reason: To ensure visual privacy within the development.

91. Courtyard fencing

The courtyard fencing shall have a maximum height of 1.2m above ground level and a 30% transparent component.

Reason: To ensure that the development contributes to the quality and amenity of communal and private open spaces.

92. Rail noise attenuation

The recommendations made in Atkins Acoustics' Rail and Vibration Assessment Report dated 31 March 2008 shall be carried out.

Reason: To attenuate rail noise

93. No door restricting internal waste collection in basement

At all times, the basement garbage storage and collection area is to be accessible by Council's Waste Collection Services. No doors, grilles, gates or other devices shall be provided in any location which would prevent this service. Where a gate, door or the like is to be erected, unimpeded access to the garbage collection point is to be provided by other means through written agreement with Council's Waste Collection Services.

Reason: To facilitate access to the garbage collection point.

GB.2 **14 to 18 Coonanbarra Road, Wahroonga - Demolition of Existing Dwellings & Construction of Two Residential Flat Buildings comprising 15 Units & Basement Car Parking**

File: DA0272/08

Applicant: Max Lucas, c/- Smyth Planning

To determine development application No. 0272/08, which seeks consent for demolition of existing dwellings and construction of two residential flat buildings comprising 15 units and basement car parking

Recommendation:

THAT the Ku-ring-gai Planning Panel, as the consent authority, is of the opinion that the objections under *State Environmental Planning Policy No.1 – Development Standards* to Clauses 25V(2)(e), 25V(2)(f) and 25V(2)(h) of the Ku-ring-gai Planning Scheme Ordinance are well founded. The Ku-ring-gai Planning Panel is also of the opinion that strict compliance with the development standards is unreasonable and unnecessary in the circumstances of this case as the proposal will result in an improved outcome consistent with aims and objectives of the control and future vision for the subject site.

AND

THAT the Ku-ring-gai Planning Panel, as the consent authority, being satisfied that the objections under SEPP No.1 are well founded and also being of the opinion that the granting of consent to DA272/08 is consistent with the aims of the Policy, grant development consent to DA272/08 for the Demolition of existing dwellings and construction of two residential flat buildings comprising 15 units and basement car parking on land at 14-18 Coonanbarra Road, Wahroonga, for a period of two (2) years from the date of the Notice of Determination, subject to the following conditions:

CONDITIONS THAT IDENTIFY APPROVED PLANS:

1. Approved architectural plans and documentation (new development)

The development must be carried out in accordance with the following plans and

documentation listed below and endorsed with Council's stamp, except where amended by other conditions of this consent:

<i>Plan no.</i>	<i>Drawn by</i>	<i>Dated</i>
Architectural Plans DA-00.1B, DA-01B, DA-02B, DA-03B, DA-04B, DA-05B, DA-06B, DA-07B,	Millennium Design Consultants	6/02/2008
Architectural Plans DA-08B, DA-09B, DA-09.1B, DA-10B	Millennium Design Consultants	14/01/2008
Stormwater Drainage Layout and sediment erosion control Plan. 1 of 3, 2 of 3 & 3 of 3 Issue A Ref No. 3908-C1	Haddad Khalil Mance Arraj Partners Consulting Engineers	8/5/2006
Landscape Plan L-01 – L-03 inclusive	Ecodesign	24/05/2006

<i>Document(s)</i>	<i>Dated</i>
Traffic Report prepared by Transport and Traffic Planning Associates.	July 2006
Arborist Report prepared by Stuart Pittendrigh	October 2005.
Access Report prepared by Access Independence Pty Ltd.	11 December 2007
Heritage Report prepared by City Plan Heritage	June 2006
Geotechnical Report prepared by Geotechnique Pty Ltd	3 May 2005
Construction Management Plan prepared by Millennium Design Consultants Pty Ltd	Undated
Waste Management Plan	Undated
Acoustic Report prepared by RSA Acoustics	April 2006

Reason: To ensure that the development is in accordance with the determination.

2. Inconsistency between documents

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent prevail.

Reason: To ensure that the development is in accordance with the determination.

CONDITIONS TO BE SATISFIED PRIOR TO DEMOLITION, EXCAVATION OR CONSTRUCTION:

3. Notice of commencement

At least 48 hours prior to the commencement of any development (including demolition, excavation, shoring or underpinning works), a notice of commencement of building or subdivision work form and appointment of the principal certifying authority form shall be submitted to Council.

Reason: Statutory requirement.

4. Notification of builder's details

Prior to the commencement of any development or excavation works, the Principal Certifying Authority shall be notified in writing of the name and contractor licence number of the owner/builder intending to carry out the approved works.

Reason: Statutory requirement.

5. Dilapidation survey and report (public infrastructure)

Prior to the commencement of any development or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures of the following public infrastructure, has been completed and submitted to Council.

Reason: Statutory requirement.

6. Public infrastructure

- Full road pavement width, including kerb and gutter, of Coonanbarra Road over the site frontage.
- All driveway crossings and laybacks opposite the subject site.

The report must be completed by a consulting structural/civil engineer. Particular attention must be paid to accurately recording (both written and photographic) existing damaged areas on the aforementioned infrastructure so that Council is fully informed when assessing any damage to public infrastructure caused as a result of the development.

The developer may be held liable to any recent damage to public infrastructure in the vicinity of the site, where such damage is not accurately recorded by the requirements of this condition prior to the commencement of works.

Note: A written acknowledgment from Council must be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any excavation works.

Reason: To record the structural condition of public infrastructure before works commence.

7. Dilapidation survey and report (private property)

Prior to the commencement of any demolition or excavation works on site, the Principal Certifying Authority shall be satisfied that a dilapidation report on the visible and structural condition of all structures upon the following lands, has been completed and submitted to Council:

20 Coonanbarra Road, Wahroonga

The dilapidation report must include a photographic survey of adjoining properties detailing their physical condition, both internally and externally, including such items as walls ceilings, roof and structural members. The report must be completed by a consulting structural/geotechnical engineer as determined necessary by that professional based on the excavations for the proposal and the recommendations of the submitted geotechnical report.

In the event that access for undertaking the dilapidation survey is denied by a property owner, the applicant must demonstrate in writing to the satisfaction of the

Principal Certifying Authority that all reasonable steps have been taken to obtain access and advise the affected property owner of the reason for the survey and that these steps have failed.

Note: A copy of the dilapidation report is to be provided to Council prior to any excavation works been undertaken. The dilapidation report is for record keeping purposes only and may be used by an applicant or affected property owner to assist in any civil action required to resolve any dispute over damage to adjoining properties arising from works.

Reason: To record the structural condition of likely affected properties before works commence.

8. Geotechnical report

Prior to the commencement of any bulk excavation works on site, the applicant shall submit to the Principal Certifying Authority, the results of the detailed geotechnical investigation comprising a minimum of three cored boreholes to at least 1 metre below the proposed basement level. The report is to address such matters as:

- appropriate excavation methods and techniques
- vibration management and monitoring
- dilapidation survey
- support and retention of excavated faces
- hydro-geological considerations

The recommendations of the report are to be implemented during the course of the works.

Reason: To ensure the safety and protection of property.

9. Access through public reserve not permitted

Access for construction purposes shall not be gained through the adjoining public reserve. Should no alternative access exist, an application for access to the construction site via the public reserve shall be submitted to Council for consideration and approval prior to the commencement of works.

Reason: To protect public reserves.

10. Construction and traffic management plan

Prior to the commencement of any works on site, the applicant must submit for review by Council's engineers a construction and traffic management plan. The following matters must be specifically addressed in the plan:

1. A plan view of the entire site and frontage roadways indicating:

- dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways
- turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site

- the locations of proposed work zones in the frontage roadways
- location of any proposed crane and concrete pump and truck standing areas on and off the site
- a dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries
- material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected
- an on-site parking area for employees, tradespersons and construction vehicles as far as possible

2. Traffic control plan(s) for the site

All traffic control plans must be in accordance with the RTA publication "Traffic Control Worksite Manual" and prepared by a suitably qualified person (minimum 'red card' qualification). The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each stage.

Approval is to be obtained from Council for any temporary road closures or crane use from public property. Applications to Council shall be made a minimum of 4 weeks prior to the activity proposed being undertaken.

3. A detailed description and route map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage must be provided.

Light traffic roads and those subject to a load or height limit must be avoided where alternate routes exist.

A copy of this route is to be made available to all contractors and shall be clearly depicted at a location within the site.

The plan must provide evidence of RTA concurrence where construction access is provided directly from or within 20m of an arterial road.

The plan must provide a schedule of site inductions to be held on regular occasions and as determined necessary to ensure all new employees are aware of their construction management obligations. These must specify that construction-related vehicles are to comply with the approved requirements.

For safety and amenity, no construction vehicle movements are to occur in Coonanbarra Road during school drop off (8.00am – 9.30am) or pick up (2.30pm – 4.00pm) times.

For those construction personnel that drive to the site, the applicant shall attempt to provide on-site parking so that their personnel's vehicles do not impact on the current parking demand in the area.

The construction and traffic management plan shall be prepared by a suitably qualified and experienced traffic consultant and be certified by this person as being in accordance with the requirements of the abovementioned documents and the requirements of this condition. The construction management measures contained in the approved plan shall be implemented in accordance

with the plan prior to the commencement of, and during, works on-site including excavation.

As the plan has a direct impact on the local road network, the plan shall be submitted to and reviewed by Council's Development Engineer. Written acknowledgment from Council's Engineer shall be obtained (attesting to this condition being appropriately satisfied) and submitted to the Principal Certifying Authority prior to the commencement of any works on site.

Reason: To ensure that appropriate measures have been considered during all phases of the construction process in a manner that maintains the environmental amenity and ensures the ongoing safety and protection of people.

11. Work zone

If a work zone is proposed, the applicant must make a written application to the Ku-ring-gai Local Traffic Committee to install the work zone. Work zones are provided specifically for the set down and pick up of materials and not for the parking of private vehicles associated with the site. Work zones will generally not be approved where there is sufficient space on-site for the setting down and picking up of goods being taken to or from a construction site.

If the work zone is approved by the Local Traffic Committee, the applicant must obtain a written copy of the related resolution from the Ku-ring-gai Local Traffic Committee and submit this to the Principal Certifying Authority prior to commencement of any works on site.

Where approval of the work zone is resolved by the Committee, the necessary work zone signage shall be installed (at the cost of the applicant) and the adopted fee paid prior to commencement of any works on site. At the expiration of the work zone approval, the applicant is required to remove the work zone signs and reinstate any previous signs at their expense.

In the event the work zone is required for a period beyond that initially approved by the Traffic Committee, the applicant shall make a payment to Council for the extended period in accordance with Council's schedule of fees and charges for work zones prior to the extended period commencing.

Reason: To ensure that appropriate measures have been made for the operation of the site during the construction phase.

12. Erosion and drainage management

Earthworks and/or demolition of any existing buildings shall not commence until an erosion and sediment control plan is submitted to and approved by the Principal Certifying Authority. The plan shall comply with the guidelines set out in the NSW Department of Housing manual "Managing Urban Stormwater: Soils and Construction" certificate. Erosion and sediment control works shall be implemented in accordance with the erosion and sediment control plan.

Reason: To preserve and enhance the natural environment.

13. Tree protection fencing excluding structure

To preserve the following tree/s, no work shall commence until the area beneath their canopy excluding that area of the proposed building shall be fenced off for the specified radius from the trunk to prevent any activities, storage or the disposal of materials within the fenced area. The fence/s shall be maintained intact until the completion of all demolition/building work on site:

Schedule Tree/location	Radius from trunk
<i>Quercus palustris</i> (Pin Oak) Tree 11, northern boundary	9m
<i>Liquidambar styraciflua</i> (Liquidambar) Tree 23, southern boundary, adjoining property	10m
<i>Podocarpus elatus</i> (Brown Pine) Tree 24, southern boundary, adjoining property	4m

Reason: To protect existing trees during the construction phase.

14. Tree protective fencing type galvanised mesh

The tree protection fencing shall be constructed of galvanised pipe at 2.4 metres spacings and connected by securely attached chain mesh fencing to a minimum of 1.8 metres in height prior to work commencing.

Reason: To protect existing trees during the construction phase.

15. Tree protection signage

Prior to works commencing, tree protection signage is to be attached to each tree protection zone, displayed in a prominent position and the sign repeated at 10 metres intervals or closer where the fence changes direction. Each sign shall contain in a clearly legible form, the following information:

- tree protection zone
- this fence has been installed to prevent damage to the trees and their growing environment both above and below ground and access is restricted
- any encroachment not previously approved within the tree protection zone shall be the subject of an arborist's report
- the arborist's report shall provide proof that no other alternative is available
- the arborist's report shall be submitted to the Principal Certifying Authority for further consultation with Council
- The name, address, and telephone number of the developer.

Reason: To protect existing trees during the construction phase.

16. Tree protection mulching

Prior to works commencing and throughout construction, the area of the tree protection zone is to be mulched to a depth of 100mm with composted organic material being 75% Eucalyptus leaf litter and 25% wood.

Reason: To protect existing trees during the construction phase.

17. Tree protection – avoiding soil compaction

To preserve the following tree/s and avoid soil compaction, no work shall commence until temporary measures to avoid soil compaction (eg rumble boards) beneath the canopy of the following tree/s is/are installed:

Schedule

Tree/Location

Trees 13, 14, 15 and 16/ western boundary, Archdale Park

Reason: To protect existing trees during the construction phase.

18. Tree fencing inspection

Upon installation of the required tree protection measures, an inspection of the site by the Principal Certifying Authority is required to verify that tree protection measures comply with all relevant conditions.

Reason: To protect existing trees during the construction phase.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE:

19. Architectural design changes

In order to ensure the privacy between Buildings A and B, the windows to the bathrooms on the southern elevation of Building A are to be of obscure or translucent glazing. Details of these amendments are to be provided to the PCA prior to the release of the Construction Certificate.

Reason: To ensure adequate privacy measures between the buildings within the development.

20. Consolidation of lots

Prior to issue of the Construction Certificate, the applicant must consolidate the existing Torrens Title lots which will form the development site. Evidence of lot consolidation, in the form of a plan registered with Department of Lands, must be submitted to the Principal Certifying Authority.

Reason: To ensure continuous structures will not be placed across boundaries.

21. Landscape design changes

To ensure adequate landscape amenity for the site, the following private courtyards are to be amended to ensure that the proposed screen planting and tree replenishment is within the ownership of the body corporate. The private courtyards are to be reduced in size as follows:

1. The courtyard for Unit 2 and Unit 3 in Block A within the side setback are to not encroach closer than 3 metres from the western site boundary.

- To preserve the ongoing viability of the following tree, the private courtyard to Unit 1 in Block B is to be set back a minimum of 2 metres from the south and western side of the tree as measured from the centre of the trunk:

Schedule

Tree/location

Radius from trunk

Quercus palustris (Pin Oak) Tree 11, northern boundary

9m

Note: The amended plans must be submitted to and approved by the Principal Certifying Authority prior to the release of the Construction Certificate.

Reason: To ensure the development is in accordance with the determination.

22. Amendments to approved plans

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that Section AA on approved plan DA10B, drawn by Millenium Design Consultants, and dated 6/02/08 is amended to show the increased setback of the basement car park of Building A, to be consistent with the section line shown on the approved floor plans. Details are to be provided prior to the release of the Construction Certificate.

Reason: To ensure the plans are consistency in the approved plans.

23. Amendments to approved landscape plan

Prior to the issue of a Construction Certificate, the Certifying Authority shall be satisfied that the approved landscape plans, listed below and endorsed with Council's stamp, have been amended in accordance with the requirements of this condition as well as other conditions of this consent:

Plan no.	Drawn by	Dated
L01/1,L02/1,L03/1	Ecodesign	1/02/08

The above landscape plan(s) shall be amended in the following ways:

- To preserve neighbour amenity and enable sufficient area for screen planting, the proposed path is not to encroach within 3m of southern site boundary.
- Proposed planting of 4 *Brachychiton acerifolius* (Flame Tree) to southern boundary is to be substituted with 3 *Waterhousia floribunda* (Weeping Lillypilly) or similar.
- Proposed planting of 1 *Eucalyptus saligna* (Sydney Blue Gum) to Block B along the western boundary to Archdale Park is to be substituted with 3 *Syncarpia glomulifera* (Turpentine).
- Proposed planting of *Leptospermum petersonii* (Lemon Scented Tea Tree) to western boundary to Archdale Park and northern boundary to Archdale Walk, is to be substituted with small trees such as *Backhousia myrtifolia* (Lemon Secented Backhousia), *Elaeocarpus reticulatus* (Blueberry Ash) or similar in association with shrub species.
- Proposed planting of *Elaeocarpus eumundii* (Eumundii Quandong) to western boundary of Block B, is to be substituted with small trees such as *Backhousia myrtifolia* (Lemon Scented Backhousia), *Elaeocarpus reticulatus* (Blueberry Ash) or similar in association with shrub species.

6. Proposed planting of *Grevillea (Honey Gem)* to western boundary to Archdale Park is to be substituted with *Pittosporum revolutum* (Yellow Pittosporum), *Notolaea longifolia* (Large Mock Olive) or similar.
7. Proposed planting of *Acmena smithii* (Hedgemaster) to northern boundary to Archdale Park is to be substituted with *Pittosporum revolutum* (Yellow Pittosporum), *Notolaea longifolia* (Large Mock Olive) or similar.
8. Proposed planting of *Strelitzia* (Bird of Paradise) to western boundary of Block B is to be substituted with small trees such as *Backhousia myrtifolia* (Lemon Scented Backhousia), *Elaeocarpus reticulatus* (Blueberry Ash) or similar in association with shrub species.

Prior to the issue of the Construction Certificate, the Principal Certifying Authority shall be satisfied that the landscape plan has been amended as required by this condition.

Note: An amended landscape plan, prepared by a landscape architect or qualified landscape designer shall be submitted to the Certifying Authority.

Reason: To ensure adequate landscape amenity.

24. Long service levy

In accordance with Section 109F(i) of the Environmental Planning and Assessment Act a Construction Certificate shall not be issued until any long service levy payable under Section 34 of the Building and Construction Industry Long Service Payments Act 1986 (or where such levy is payable by instalments, the first instalment of the levy) has been paid. Council is authorised to accept payment. Where payment has been made elsewhere, proof of payment is to be provided to Council.

Reason: Statutory requirement.

25. Builder's indemnity insurance

The applicant, builder, developer or person who does the work on this development, must arrange builder's indemnity insurance and submit the certificate of insurance in accordance with the requirements of Part 6 of the Home Building Act 1989 to the Certifying Authority for endorsement of the plans accompanying the Construction Certificate.

It is the responsibility of the applicant, builder or developer to arrange the builder's indemnity insurance for residential building work over the value of \$12,000. The builder's indemnity insurance does not apply to commercial or industrial building work or to residential work valued at less than \$12,000, nor to work undertaken by persons holding an owner/builder's permit issued by the Department of Fair Trading (unless the owner/builder's property is sold within 7 years of the commencement of the work).

Reason: Statutory requirement.

26. Outdoor lighting

Prior to the issue of a Construction Certificate, the Certifying Authority shall be

satisfied that all outdoor lighting will comply with AS/NZ1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Note: Details demonstrating compliance with these requirements are to be submitted prior to the issue of a Construction Certificate.

Reason: To provide high quality external lighting for security without adverse affects on public amenity from excessive illumination levels.

27. Access for people with disabilities (residential)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that access for people with disabilities to and from and between the public domain, residential units and all common open space areas is provided. Consideration must be given to the means of dignified and equitable access.

Compliant access provisions for people with disabilities shall be clearly shown on the plans submitted with the Construction Certificate. All details shall be provided to the Principal Certifying Authority prior to the issue of the Construction Certificate. All details shall be prepared in consideration of the Disability Discrimination Act, and the relevant provisions of AS1428.1, AS1428.2, AS1428.4 and AS 1735.12.

Reason: To ensure the provision of equitable and dignified access for all people in accordance with disability discrimination legislation and relevant Australian Standards.

28. Adaptable units

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that the nominated adaptable units within the development application, Unit 2 and 5, are designed as adaptable housing in accordance with the provisions of Australian Standard AS4299-1995: Adaptable Housing.

Note: Evidence from an appropriately qualified professional demonstrating compliance with this control is to be submitted to and approved by the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Disabled access & amenity.

29. Stormwater management plan

Prior to issue of the Construction Certificate, the applicant must submit, for approval by the Principal Certifying Authority, scale construction plans and specifications in relation to the stormwater management and disposal system for the development. The plan(s) must include the following detail:

- exact location and reduced level of discharge point to the public drainage system
- Layout of the property drainage system components, including but not limited to (as required) gutters, downpipes, spreaders, pits, swales, kerbs, cut-off and intercepting drainage structures, subsoil drainage, flushing facilities and all ancillary stormwater plumbing - all designed for a 235mm/hour rainfall

intensity for a duration of five (5) minutes (1:50 year storm recurrence)

- location(s), dimensions and specifications for the required rainwater storage and reuse tanks and systems and where proprietary products are to be used, manufacturer specifications or equivalent shall be provided
- specifications for reticulated pumping facilities (including pump type and manufacturer specifications) and ancillary plumbing to fully utilise rainwater in accordance with Ku-ring-gai Council Development Control Plan 47 and/or BASIX commitments
- details of the required on-site detention tanks required by Ku-ring-gai Water Management DCP 47, including dimensions, materials, locations, orifice and discharge control pit details as required (refer Chapter 6 and Appendices 2, 3 and 5 of DCP 47 for volume, PSD and design requirements)
- the required basement stormwater pump-out system is to cater for driveway runoff and subsoil drainage (refer appendix 7.1.1 of Development Control Plan 47 for design)

The above construction drawings and specifications are to be prepared by a qualified and experienced civil/hydraulic engineer in accordance with Council's Water Management Development Control Plan 47, Australian Standards 3500.2 and 3500.3 - Plumbing and Drainage Code and the Building Code of Australia. The plans may be generally based on the plans by Haddad Khaicy Mance Arraj submitted with the development application, which are to be advanced as necessary for construction certificate issue purposes.

Reason: To protect the environment.

30. Stormwater retention

Prior to the issue of a Construction Certificate, the Principal Certifying Authority is to be satisfied that:

1. A mandatory rainwater retention and re-use system, comprising storage tanks and ancillary plumbing is provided. The minimum total storage volume of the rainwater tank system, and the prescribed re-use of the water on site must satisfy all relevant BASIX commitments and the requirements specified in Chapter 6 of Ku-ring-gai Water Management Development Control Plan 47; and
2. An on-site stormwater detention system must be provided to control the rate of runoff leaving the site. The minimum volume of the required on-site detention system must be determined in accordance with Chapter 6 of the Ku-ring-gai Council Water Management Development Control Plan 47 - having regard to the specified volume concession offered in lieu of installing rainwater retention tanks. The on-site detention system must be designed by a qualified civil/hydraulic engineer and must satisfy the design controls set out in Appendix 5 of DCP 47.

Reason: To protect the environment.

31. Excavation for services

Prior to the issue of the Construction Certificate, the Principal Certifying shall be satisfied that no proposed underground services (ie. water, sewerage, drainage, gas

or other service) unless previously approved by conditions of consent, are located beneath the canopy of any tree protected under Council's Tree Preservation Order, located on the subject allotment and adjoining allotments.

Note: A plan detailing the routes of these services and trees protected under the Tree Preservation Order, shall be submitted to the Principal Certifying Authority.

Reason: To ensure the protection of trees.

32. Noise from road and rail (residential only)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that the building is acoustically designed and constructed to meet the requirements of AS 2107 and the Environment Protection Authority's Guidelines for Acoustic Privacy within Premises. Alternatively, a certificate from an appropriately qualified acoustic engineer certifying that the development will comply with the above requirements shall be submitted to the Principal Certifying Authority for approval prior to the issue of the Construction Certificate.

Note: Plans and specifications of the required acoustic design shall be prepared by a practicing acoustic engineer and shall be submitted to the Principal Certifying Authority.

Reason: To minimise the impact of noise from the adjoining major road or rail corridor on the occupants of the development.

33. Noise from plant in residential zone

Where any form of mechanical ventilation equipment or other noise generating plant is proposed as part of the development, prior to the issue of the Construction Certificate the Certifying Authority, shall be satisfied that the operation of an individual piece of equipment or operation of equipment in combination will not exceed more than 5dB(A) above the background level during the day when measured at the site's boundaries and shall not exceed the background level at night (10.00pm – 6.00 am) when measured at the boundary of the site.

C1. Note: A certificate from an appropriately qualified acoustic engineer is to be submitted with the Construction Certificate, certifying that all mechanical ventilation equipment or other noise generating plant in isolation or in combination with other plant will comply with the above requirements.

Reason: To comply with best practice standards for residential acoustic amenity.

34. Location of plant (residential flat buildings)

Prior to the issue of the Construction Certificate, the Certifying Authority shall be satisfied that all plant and equipment (including but not limited to air conditioning equipment) is located within the basement.

C1. Note: Architectural plans identifying the location of all plant and equipment shall be provided to the Certifying Authority.

Reason: To minimise impact on surrounding properties, improved visual appearance and amenity for locality.

35. Driveway crossing levels

Prior to issue of the Construction Certificate, driveway and associated footpath levels for any new, reconstructed or extended sections of driveway crossings between the property boundary and road alignment must be obtained from Ku-ring-gai Council. Such levels are only able to be issued by Council under the Roads Act 1993. All footpath crossings, laybacks and driveways are to be constructed according to Council's specifications "Construction of Gutter Crossings and Footpath Crossings".

Specifications are issued with alignment levels after completing the necessary application form at Customer Services and payment of the assessment fee. When completing the request for driveway levels application from Council, the applicant must attach a copy of the relevant development application drawing which indicates the position and proposed level of the proposed driveway at the boundary alignment.

This development consent is for works wholly within the property. Development consent does not imply approval of footpath or driveway levels, materials or location within the road reserve, regardless of whether this information is shown on the development application plans. The grading of such footpaths or driveways outside the property shall comply with Council's standard requirements. The suitability of the grade of such paths or driveways inside the property is the sole responsibility of the applicant and the required alignment levels fixed by Council may impact upon these levels.

The construction of footpaths and driveways outside the property in materials other than those approved by Council is not permitted.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

36. Driveway grades – basement car parks

Prior to the issue of the Construction Certificate, longitudinal driveway sections are to be prepared by a qualified civil/traffic engineer and be submitted for to and approved by the Certifying Authority. These profiles are to be at 1:100 scale along both edges of the proposed driveway, starting from the centreline of the frontage street carriageway to the proposed basement floor level. The traffic engineer shall provide specific written certification on the plans that:

- vehicular access can be obtained using grades of 20% (1 in 5) maximum and
- all changes in grade (transitions) comply with Australian Standard 2890.1 – "Off-street car parking" (refer clause 2.5.3) to prevent the scraping of the underside of vehicles.

If a new driveway crossing is proposed, the longitudinal sections must incorporate the driveway crossing levels as issued by Council upon prior application.

Reason: To provide suitable vehicular access without disruption to pedestrian and vehicular traffic.

37. Basement car parking details

Prior to issue of the Construction Certificate, certified parking layout plan(s) to scale showing all aspects of the vehicle access and accommodation arrangements must be submitted to and approved by the Certifying Authority. A qualified civil/traffic engineer must review the proposed vehicle access and accommodation layout and provide written certification on the plans that:

- all parking space dimensions, driveway and aisle widths, driveway grades, transitions, circulation ramps, blind aisle situations and other trafficked areas comply with Australian Standard 2890.1 – 2004 “Off-street car parking”
- a clear height clearance of 2.5 metres (required under DCP40 for waste collection trucks) is provided over the designated garbage collection truck manoeuvring areas within the basement
- no doors or gates are provided in the access driveways to the basement car park which would prevent unrestricted access for internal garbage collection at any time from the basement garbage storage and collection area
- the vehicle access and accommodation arrangements are to be constructed and marked in accordance with the certified plans

Reason: To ensure that parking spaces are in accordance with the approved development.

38. Car parking allocation

Car parking within the development shall be allocated in the following way:

Resident car spaces	30
Visitor spaces	4
Total spaces	34

Each adaptable dwelling must be provided with car parking complying with the dimensional and location requirements of AS2890.1 – parking spaces for people with disabilities.

At least one visitor space shall also comply with the dimensional and location requirements of AS2890.1 – parking spaces for people with disabilities.

Consideration must be given to the means of access from disabled car parking spaces to other areas within the building and to footpath and roads and shall be clearly shown on the plans submitted with the Construction Certificate.

Reason: To ensure equity of access and appropriate facilities are available for people with disabilities in accordance with federal legislation.

39. Energy Australia requirements

Prior to issue of the Construction Certificate, the applicant must contact Energy Australia regarding power supply for the subject development. A written response detailing the full requirements of Energy Australia (including any need for underground cabling, substations or similar within or in the vicinity the development) shall be submitted to the Principal Certifying Authority for approval prior to issue of

the Construction Certificate.

Any structures or other requirements of Energy Australia shall be indicated on the plans issued with the Construction Certificate, to the satisfaction of the Principal Certifying Authority and Energy Australia. The requirements of Energy Australia must be met in full prior to issue of the Occupation Certificate.

Reason: To ensure compliance with the requirements of Energy Australia.

40. Utility provider requirements

Prior to issue of the Construction Certificate, the applicant must make contact with all relevant utility providers whose services will be impacted upon by the development. A written copy of the requirements of each provider, as determined necessary by the Certifying Authority, must be obtained. All utility services or appropriate conduits for the same must be provided by the developer in accordance with the specifications of the utility providers.

Reason: To ensure compliance with the requirements of relevant utility providers.

41. Underground services

All electrical services (existing and proposed) shall be undergrounded from the proposed building on the site to the appropriate power pole(s) or other connection point. Undergrounding of services must not disturb the root system of existing trees and shall be undertaken in accordance with the requirements of the relevant service provided. Documentary evidence that the relevant service provider has been consulted and that their requirements have been met are to be provided to the Certifying Authority prior to the issue of the Construction Certificate. All electrical and telephone services to the subject property must be placed underground and any redundant poles are to be removed at the expense of the applicant.

Reason: To provide infrastructure that facilitates the future improvement of the streetscape by relocation of overhead lines below ground.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE OR PRIOR TO DEMOLITION, EXCAVATION OR CONSTRUCTION (WHICHEVER COMES FIRST):

42. Infrastructure restorations fee

To ensure that damage to Council Property as a result of construction activity is rectified in a timely matter:

- a) All work or activity taken in furtherance of the development the subject of this approval must be undertaken in a manner to avoid damage to Council Property and must not jeopardise the safety of any person using or occupying the adjacent public areas.
- b) The applicant, builder, developer or any person acting in reliance on this approval shall be responsible for making good any damage to Council Property, and for the removal from Council Property of any waste bin, building materials, sediment, silt, or any other material or article.

- c) The Infrastructure Restoration Fee must be paid to the Council by the applicant prior to both the issue of the Construction Certificate and the commencement of any earthworks or construction.
- d) In consideration of payment of the Infrastructure Restorations Fee, Council will undertake such inspections of Council Property as Council considers necessary and also undertake, on behalf of the applicant, such restoration work to Council Property, if any, that Council considers necessary as a consequence of the development. The provision of such restoration work by the Council does not absolve any person of the responsibilities contained in (a) to (b) above. Restoration work to be undertaken by the Council referred to in this condition is limited to work that can be undertaken by Council at a cost of not more than the Infrastructure Restorations Fee payable pursuant to this condition.

e) In this condition:

“Council Property” includes any road, footway, footpath paving, kerbing, guttering, crossings, street furniture, seats, letter bins, trees, shrubs, lawns, mounds, bushland, and similar structures or features on any road or public road within the meaning of the Local Government Act 1993 (NSW) or any public place; and

“Infrastructure Restoration Fee” means the Infrastructure Restorations Fee calculated in accordance with the Schedule of Fees & Charges adopted by Council as at the date of payment and the cost of any inspections required by the Council of Council Property associated with this condition.

Reason: To maintain public infrastructure.

43. Section 94 contribution – residential development

A contribution pursuant to section 94 of the Environmental Planning and Assessment Act as specified in Ku-ring-gai Section 94 Contributions Plan 2004-2009 for the services detailed in column A and for the amount detailed in Column B is required.

Column A	Column B
community facilities	\$13,137.89
park acquisition and embellishment works	\$183,247.57
park embellishment works	\$31,689.09
sportsgrounds works	\$44,836.84
aquatic / leisure centres	\$2,654.33
traffic and transport	\$3,744.82
section 94 Plan administration	\$3,357.04
Total contribution is:	\$282,667.57

The contribution shall be paid to Council prior to the commencement of any development (including demolition) or prior to the issue of the Construction Certificate (whichever comes first). The charges may vary at the time of payment in accordance with Council’s Section 94 Contributions Plan to reflect changes in land values, construction costs and the consumer price index. Prior to payment, you are advised to check the contribution amount required with Council.

Reason: To ensure the provision, extension or augmentation of community facilities, recreation facilities, open space and administration that will, or are likely to be, required as a consequence of the development.

CONDITIONS TO BE SATISFIED DURING THE DEMOLITION, EXCAVATION AND CONSTRUCTION PHASES:

44. Approved plans to be on site

A copy of all approved and certified plans, specifications and documents incorporating conditions of consent and certification (including the Construction Certificate if required for the work) shall be kept on site at all times during the demolition, excavation and construction phases and must be readily available to any officer of Council or the Principal Certifying Authority.

Reason: To ensure that the development is in accordance with the determination.

45. Engineering fees

For the purpose of any development related inspections by Ku-ring-gai Council engineers, the corresponding fees set out in Councils adopted *Schedule of Fees and Charges* are payable to Council. A re-inspection fee per visit may be charged where work is unprepared at the requested time of inspection, or where remedial work is unsatisfactory and a further inspection is required. Engineering fees must be paid in full prior to any final consent from Council.

Reason: To protect public infrastructure.

46. Prescribed conditions

The applicant shall comply with any relevant prescribed conditions of development consent under clause 98 of the Environmental Planning and Assessment Regulation. For the purposes of section 80A (11) of the Environmental Planning and Assessment Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- The work must be carried out in accordance with the requirements of the Building Code of Australia
- In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any works commence.

Reason: Statutory requirement.

47. Statement of compliance with Australian Standards

The demolition work shall comply with the provisions of Australian Standard AS2601: 2001 The Demolition of Structures. The work plans required by AS2601: 2001 shall be accompanied by a written statement from a suitably qualified person that the proposal contained in the work plan comply with the safety requirements of the Standard. The work plan and the statement of compliance shall be submitted to the

satisfaction of the Principal Certifying Authority prior to the commencement of any works.

Reason: To ensure compliance with the Australian Standards.

48. Demolition, excavation and construction work hours

Demolition, excavation, construction work and deliveries of building material and equipment must not take place outside the hours of 7.00am to 5.00pm Monday to Friday and 8.00am to 12.00pm Saturday. No work and no deliveries are to take place on Sundays and public holidays.

Excavation or removal of any materials using machinery of any kind, including compressors and jack hammers, must be limited to between 7.30am and 5.00pm Monday to Friday, with a respite break of 45 minutes between 12 noon and 1.00pm.

Where it is necessary for works to occur outside of these hours (i.e. concrete pours and standing of plant), approval for such will be subject to the issue of an "outside of hours works permit" from Council as well as notification of the surrounding properties likely to be affected by the proposed works.

Note: Failure to obtain a permit for work outside of the approved hours will result in on the spot fines being issued.

Reason: To ensure reasonable standards of amenity for occupants of neighbouring properties.

49. Construction noise

During excavation, demolition and construction phases, noise generated from the site shall be controlled in accordance with the recommendations of the approved noise and vibration management plan.

Reason: To ensure reasonable standards of amenity to neighbouring properties.

50. Site notice

A site notice shall be erected on the site prior to any work commencing and shall be displayed throughout the works period.

The site notice must:

- be prominently displayed at the boundaries of the site for the purposes of informing the public that unauthorised entry to the site is not permitted
- display project details including, but not limited to the details of the builder, Principal Certifying Authority and structural engineer
- be durable and weatherproof
- display the approved hours of work, the name of the site/project manager, the responsible managing company (if any), its address and 24 hour contact phone number for any inquiries, including construction/noise complaint are to be displayed on the site notice
- be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted

Reason: To ensure public safety and public information.

51. Dust control

During excavation, demolition and construction, adequate measures shall be taken to prevent dust from affecting the amenity of the neighbourhood. The following measures must be adopted:

- physical barriers shall be erected at right angles to the prevailing wind direction or shall be placed around or over dust sources to prevent wind or activity from generating dust
- earthworks and scheduling activities shall be managed to coincide with the next stage of development to minimise the amount of time the site is left cut or exposed
- all materials shall be stored or stockpiled at the best locations
- the ground surface should be dampened slightly to prevent dust from becoming airborne but should not be wet to the extent that run-off occurs
- all vehicles carrying spoil or rubble to or from the site shall at all times be covered to prevent the escape of dust
- all equipment wheels shall be washed before exiting the site using manual or automated sprayers and drive-through washing bays
- gates shall be closed between vehicle movements and shall be fitted with shade cloth
- cleaning of footpaths and roadways shall be carried out daily

Reason: To protect the environment and amenity of surrounding properties.

52. Post-construction dilapidation report

If necessary, the applicant shall engage a suitably qualified person to prepare a post construction dilapidation report at the completion of the construction works. This report is to ascertain whether the construction works created any structural damage to adjoining buildings, infrastructure and roads. The report is to be submitted to the Principal Certifying Authority. In ascertaining whether adverse structural damage has occurred to adjoining buildings, infrastructure and roads, the Principal Certifying Authority must:

- compare the post-construction dilapidation report with the pre-construction dilapidation report
- have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.

A copy of this report is to be forwarded to Council at the completion of the construction works.

Reason: Management of records.

53. Further geotechnical input

The geotechnical and hydro-geological works implementation, inspection, testing and monitoring program for the excavation and construction works must be in accordance with the report by Geotechnique. Over the course of the works, a qualified

geotechnical/hydro-geological engineer must complete the following:

- further geotechnical investigations and testing recommended in the above report(s) and as determined necessary
- further monitoring and inspection at the hold points recommended in the above report(s) and as determined necessary
- written report(s) including certification(s) of the geotechnical inspection, testing and monitoring programs

Reason: To ensure the safety and protection of property.

54. Compliance with submitted geotechnical report

A contractor with specialist excavation experience must undertake the excavations for the development and a suitably qualified and consulting geotechnical engineer must oversee excavation.

Geotechnical aspects of the development work, namely:

- appropriate excavation method and vibration control
- support and retention of excavated faces
- hydro-geological considerations

must be undertaken in accordance with the recommendations of the geotechnical report prepared by Geotechnique. Approval must be obtained from all affected property owners, including Ku-ring-gai Council, where rock anchors (both temporary and permanent) are proposed below adjoining property(ies).

Reason: To ensure the safety and protection of property.

55. Use of road or footpath

During excavation, demolition and construction phases, no building materials, plant or the like are to be stored on the road or footpath without written approval being obtained from Council beforehand. The pathway shall be kept in a clean, tidy and safe condition during building operations. Council reserves the right, without notice, to rectify any such breach and to charge the cost against the applicant/owner/builder, as the case may be.

Reason: To ensure safety and amenity of the area.

56. Guarding excavations

All excavation, demolition and construction works shall be properly guarded and protected with hoardings or fencing to prevent them from being dangerous to life and property.

Reason: To ensure public safety.

57. Toilet facilities

During excavation, demolition and construction phases, toilet facilities are to be provided, on the work site, at the rate of one toilet for every 20 persons or part of 20

persons employed at the site.

Reason: Statutory requirement.

58. Recycling of building material (general)

During demolition and construction, the Principal Certifying Authority shall be satisfied that building materials suitable for recycling have been forwarded to an appropriate registered business dealing in recycling of materials. Materials to be recycled must be kept in good order.

Reason: To facilitate recycling of materials.

59. Construction signage

All construction signs must comply with the following requirements:

- are not to cover any mechanical ventilation inlet or outlet vent
- are not illuminated, self-illuminated or flashing at any time
- are located wholly within a property where construction is being undertaken
- refer only to the business(es) undertaking the construction and/or the site at which the construction is being undertaken
- do not exceed 2.5m²
- are removed within 14 days of the completion of all construction works

Reason: To ensure compliance with Council's controls regarding signage.

60. Maintenance period for works in public road

A maintenance period of six (6) months applies to all work in the public road reserve carried out by the applicant - after the works have been completed to the satisfaction of Ku-ring-gai Council. In that maintenance period, the applicant shall be liable for any section of the public infrastructure work which fails to perform in the designed manner, or as would reasonably be expected under the operating conditions. The maintenance period shall commence once the applicant receives a formal letter from Council stating that the works involving public infrastructure have been completed satisfactorily.

Reason: To protect public infrastructure.

61. Road reserve safety

All public footways and roadways fronting and adjacent to the site must be maintained in a safe condition at all times during the course of the development works. Construction materials must not be stored in the road reserve. A safe pedestrian circulation route and a pavement/route free of trip hazards must be maintained at all times on or adjacent to any public access ways fronting the construction site. Where public infrastructure is damaged, repair works must be carried out when and as directed by Council officers. Where pedestrian circulation is diverted on to the roadway or verge areas, clear directional signage and protective barricades must be installed in accordance with AS1742-3 (1996) "Traffic Control Devices for Work on Roads". If pedestrian circulation is not satisfactorily maintained across the site frontage, and action is not taken promptly to rectify the defects,

Council may undertake proceedings to stop work.

Reason: To ensure safe public footways and roadways during construction.

62. Road repairs necessitated by excavation and construction works

It is highly likely that damage will be caused to the roadway at or near the subject site as a result of the construction (or demolition or excavation) works. The applicant, owner and builder (and demolition or excavation contractor as appropriate) will be held responsible for repair of such damage, regardless of the Infrastructure Restorations Fee paid (this fee is to cover wear and tear on Council's wider road network due to heavy vehicle traffic, not actual major damage).

Section 102(1) of the Roads Act states "A person who causes damage to a public road is liable to pay to the appropriate roads authority the cost incurred by that authority in making good the damage."

Council will notify when road repairs are needed, and if they are not carried out within 48 hours, then Council will proceed with the repairs, and will invoice the applicant, owner and relevant contractor for the balance.

Reason: To protect public infrastructure.

63. Services

Where required, the adjustment or inclusion of any new utility service facilities must be carried out by the applicant and in accordance with the requirements of the relevant utility authority. These works shall be at no cost to Council. It is the applicant's full responsibility to make contact with the relevant utility authorities to ascertain the impacts of the proposal upon utility services (including water, phone, gas and the like). Council accepts no responsibility for any matter arising from its approval to this application involving any influence upon utility services provided by another authority.

Reason: Provision of utility services.

64. Erosion control

Temporary sediment and erosion control and measures are to be installed prior to the commencement of any works on the site. These measures must be maintained in working order during construction works up to completion. All sediment traps must be cleared on a regular basis and after each major storm and/or as directed by the Principal Certifying Authority and Council officers.

Reason: To protect the environment from erosion and sedimentation.

65. Drainage to street

Stormwater runoff from all new impervious areas and subsoil drainage systems shall be piped to the street drainage system. New drainage line connections to the street drainage system shall conform and comply with the requirements of Sections 5.3 and 5.4 of Ku-ring-gai Water Management Development Control Plan No. 47.

Reason: To protect the environment.

66. Grated drain at garage

A 200mm wide grated channel/trench drain, with a heavy-duty removable galvanised grate is to be provided in front of the garage door/basement parking slab to collect driveway runoff. The channel drain shall be connected to the main drainage system and must have an outlet of minimum diameter 150mm to prevent blockage by silt and debris.

Reason: Stormwater control.

67. Sydney Water Section 73 Compliance Certificate

The applicant must obtain a **Section 73 Compliance Certificate** under the *Sydney Water Act 1994*. An application must be made through an authorised Water Servicing Co-ordinator. The applicant is to refer to "Your Business" section of Sydney Water's web site at www.sydneywater.com.au then the "e-develop" icon or telephone 13 20 92. Following application a "Notice of Requirements" will detail water and sewer extensions to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Reason: Statutory requirement.

68. Arborist's report

The trees to be retained shall be inspected, monitored and treated by a qualified arborist during and after completion of development works to ensure their long term survival. Regular inspections and documentation from the arborist to the Principal Certifying Authority are required at the following times or phases of work:

Schedule

Tree/location

Quercus palustris (Pin Oak) Tree 11, northern boundary
Liquidambar styraciflua (Liquidambar) Tree 23, southern boundary, adjoining property
Podocarpus elatus (Brown Pine) Tree 24, southern boundary, adjoining property

Time of inspection

Commencement of excavation, erection of scaffolding
Commencement of excavation, erection of scaffolding
Commencement of excavation, erection of scaffolding

Reason: To ensure protection of existing trees.

69. Trees on nature strip

Removal/pruning of the following tree/s from Council's nature strip to permit vehicular access shall be undertaken at no cost to Council by an experienced tree removal contractor/arborist holding public liability insurance amounting to a minimum cover of \$10,000,000.

Schedule

Tree/location

Cinnamomum camphora (Camphor laurel) Tree 19
Cinnamomum camphora (Camphor laurel) Tree 20

Reason: To ensure protection of existing trees.

70. Canopy/root pruning

Canopy and/or root pruning of the following tree(s) which is necessary to accommodate the approved building works shall be undertaken by an experienced an AQF level 3 Arborist and in accordance with the reduction pruning clause of AS4373-2007. All other branches are to be tied back and protected during construction, under the supervision of a qualified arborist.

Schedule	Tree/location	Tree works
	<i>Quercus palustris</i> (Pin Oak) Tree 11, northern boundary	Minor pruning
	<i>Liquidambar styraciflua</i> (Liquidambar) Tree 23	Minor pruning
	<i>Podocarpus elatus</i> (Brown Pine) Tree 24	Minor pruning

Reason: To protect the environment.

71. Treatment of tree roots

If tree roots are required to be severed for the purposes of constructing the approved works, they shall be cut cleanly by hand, by an experienced arborist/horticulturist with a minimum qualification of horticulture certificate or tree surgery certificate

Reason: To protect existing trees.

72. Cutting of tree roots

No tree roots of 30mm or greater in diameter located within the specified radius of the trunk(s) of the following, tree(s) shall be severed or injured in the process of any works during the construction period.

Schedule	Tree/location	Radius from trunk
	<i>Quercus palustris</i> (Pin Oak) Tree 11, northern boundary	9m

Reason: To protect existing trees.

73. Approved tree works

Approval is given for the following works to be undertaken to trees on the site. Tree numbers refer to arborist report prepared by Stuart Pittendrigh, dated October 2005 and Letter from Ecodesign dated 10 August 2007.

Schedule	Tree location	Approved tree works
	<i>Cinnamomum camphora</i> (Camphor laurel) Tree 1-9	Removal
	<i>Ceratopetalum gummiferum</i> (NSW Christmas Bush) Tree 10	Removal
	<i>Ulmus parvifolia</i> (Chinese Elm) Tree 11	Removal
	<i>Cinnamomum camphora</i> (Camphor laurel) Tree 17	Removal
	<i>Quercus palustris</i> (Pin Oak) Tree 11, northern	Minor pruning for scaffolding -

Schedule
Tree location
boundary

Approved tree works

affected branches be pruned by an AQF level 3 Arborist and in accordance with the reduction pruning clause of AS4373-2007. Work to be carried out by Arborist experienced in pruning oaks.

Liquidambar styraciflua (Liquidambar) Tree 23

Minor pruning for scaffolding - affected branches be pruned by an AQF level 3 Arborist and in accordance with the reduction pruning clause of AS4373-2007.

Podocarpus elatus (Brown Pine) Tree 24

Minor pruning for scaffolding - affected branches be pruned by an AQF level 3 Arborist and in accordance with the reduction pruning clause of AS4373-2007.

Removal or pruning of any other tree on the site is not approved.

Reason: To ensure that the development is in accordance with the determination of Council.

74. Excavation near trees

No mechanical excavation shall be undertaken within the specified radius of the trunk(s) of the following tree(s) until root pruning by hand along the perimeter line of such works is completed:

Schedule
Tree/location

Radius from trunk

Quercus palustris (Pin Oak) Tree 11, northern boundary

9m

Reason: To protect existing trees.

75. Hand excavation

All excavation within the specified radius of the trunk(s) of the following tree(s) shall be hand dug:

Schedule
Tree/location

Radius from trunk

Quercus palustris (Pin Oak) Tree 11, northern boundary

9m

Reason: To protect existing trees.

76. Thrust boring

Excavation for the installation of any services within the specified radius of the trunk(s) of the following tree(s) shall utilise the thrust boring method. Thrust boring shall be carried out at least 800mm beneath natural ground level to minimise

damage to tree(s) root system.

Schedule

Tree/location

Quercus palustris (Pin Oak) Tree 11, northern boundary

Radius from trunk

9m

Reason: To protect existing trees.

77. No storage of materials beneath trees

No activities, storage or disposal of materials shall take place beneath the canopy of any tree protected under Council's Tree Preservation Order at any time.

Reason: To protect existing trees.

78. Tree planting on nature strip

The following tree species shall be planted, at no cost to Council, in the nature strip fronting the property along Coonanbarra Road. The tree(s) used shall be a minimum 25 litres container size specimen(s):

Schedule

Tree/ species

Platanus orientalis 'Digitata' (Oriental Plane Tree)

Quantity

2

Location

Coonanbarra Road – minimum 4m from proposed driveway

Reason: To provide appropriate landscaping within the streetscape.

79. Tree removal on nature strip

Following removal of the *Cinnamomum camphora* (Camphor laurel) from Council's nature strip, the nature strip shall be rehabilitated to the satisfaction of Council's Landscape Assessment Officer at no cost to Council.

Reason: To protect the streetscape.

80. Removal of refuse

All builders' refuse, spoil and/or material unsuitable for use in landscape areas shall be removed from the site on completion of the building works.

Reason: To protect the environment.

81. Canopy replenishment trees to be planted

The canopy replenishment trees to be planted shall be maintained in a healthy and vigorous condition until they attain a height of 5.0 metres whereby they will be protected by Council's Tree Preservation Order. Any of the trees found faulty, damaged, dying or dead shall be replaced with the same species

Reason: To maintain the treed character of the area.

82. Removal of noxious plants & weeds

The following noxious and/or environmental weed species shall be removed from the property prior to completion of building works:

Schedule

Plant species

Anredera cordifolia (Madeira Vine)
Asparagus asparagoides (Bridal Creeper)
Asparagus densiflorus (Asparagus Fern)
Cinnamomum camphora (Camphor laurel)
Cotoneaster sp. (Cotoneaster)
Erigeron karvinskianus (Seaside Daisy)
Hedera helix (English Ivy)
Hedychium gardnerianum (Ginger lily)
Hypochoeris radicata (Catsear)
Jasminum polyanthum (Jasminum)
Ligustrum lucidum (Large-leaved Privet)
Nephrolepis cordifolia (Fishbone fern)
Ochna serrulata (Ochna)
Taraxacum officinale (Dandelion)
Tradescantia albiflora (Wandering Jew)

Reason: To protect the environment.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE:

83. Easement for waste collection

Prior to issue of the Occupation Certificate, an easement for waste collection is to be created. This is to permit legal access for Council, Council's contractors and their vehicles over the subject property for the purpose of collecting waste from the property. The terms of the easement are to be generally in accordance with Council's draft terms for an easement for waste collection and shall be to the satisfaction of Council's Development Engineer.

Reason: To permit legal access for Council, Council's contractors and their vehicles over the subject site for waste collection.

84. Compliance with BASIX Certificate

Prior to the issue of an Occupation Certificate, the Principal Certifying Authority shall be satisfied that all commitments listed in BASIX Certificate No. 82164M have been complied with.

Reason: Statutory requirement.

85. Completion of landscape works

Prior to the release of the Occupation Certificate, the Principal Certifying Authority is to be satisfied that all landscape works, including the removal of all noxious and/or

environmental weed species, have been undertaken in accordance with the approved plan(s) and conditions of consent.

Reason: To ensure that the landscape works are consistent with the development consent.

86. Accessibility

Prior to the issue of an Occupation Certificate, the Principal Certifying Authority shall be satisfied that:

- the lift design and associated functions are compliant with AS 1735.12 & AS 1428.2
- the level and direction of travel, both in lifts and lift lobbies, is audible and visible
- the controls for lifts are accessible to all persons and control buttons and lettering are raised
- international symbols have been used with specifications relating to signs, symbols and size of lettering complying with AS 1428.2
- the height of lettering on signage is in accordance with AS 1428.1 – 1993
- the signs and other information indicating access and services incorporate tactile communication methods in addition to the visual methods

Reason: Disabled access & services.

87. Retention and re-use positive covenant

Prior to issue of the Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the property with the requirement to maintain the site stormwater retention and re-use facilities on the property.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instruments for protection of retention and re-use facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Water Management Development Control Plan No. 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the reuse and retention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents showing the covenants and restrictions must be submitted to and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

88. Provision of copy of OSD designs if Council is not the PCA

Prior to issue of the Occupation Certificate, the following must be provided to Council's Development Engineer:

- a copy of the approved Construction Certificate stormwater detention/retention

design for the site

- A copy of any works-as-executed drawings required by this consent
- The Engineer's certification of the as-built system.

Reason: For Council to maintain its database of as-constructed on-site stormwater detention systems.

89. Certification of drainage works (dual occupancies and above)

Prior to issue of the Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the stormwater drainage works have been satisfactorily completed in accordance with the approved Construction Certificate drainage plans
- the minimum retention and on-site detention storage volume requirements of BASIX and Ku-ring-gai Water Management Development Control Plan No. 47 respectively, have been achieved
- retained water is connected and available for use
- basement and subsoil areas are able to drain via a pump/sump system installed in accordance with AS3500.3 and Appendix 7.1.1 of Ku-ring-gai Water Management Development Control Plan No. 47
- all grates potentially accessible by children are secured
- components of the new drainage system have been installed by a licensed plumbing contractor in accordance with the Plumbing and Drainage Code AS3500.3 2003 and the Building Code of Australia
- all enclosed floor areas, including habitable and garage floor levels, are safeguarded from outside stormwater runoff ingress by suitable differences in finished levels, gradings and provision of stormwater collection devices

The rainwater certification sheet contained in Appendix 13 of the Ku-ring-gai Water Management Development Control Plan No. 47, must be completed and attached to the certification. Where an on-site detention system has been constructed, the on-site detention certification sheet contained in Appendix 4 of DCP 47 must also be completed and attached to the certification.

Note: Evidence from a qualified and experienced consulting civil/hydraulic engineer documenting compliance with the above is to be provided to Council prior to the issue of an Occupation Certificate.

Reason: To protect the environment.

90. WAE plans for stormwater management and disposal (dual occupancy and above)

Prior to issue of the Occupation Certificate, a registered surveyor must provide a works as executed survey of the completed stormwater drainage and management systems. The survey must be submitted to and approved by the Principal Certifying Authority prior to issue of the Occupation Certificate. The survey must indicate:

- as built (reduced) surface and invert levels for all drainage pits
- gradients of drainage lines, materials and dimensions
- as built (reduced) level(s) at the approved point of discharge to the public drainage system

- as built location and internal dimensions of all detention and retention structures on the property (in plan view) and horizontal distances to nearest adjacent boundaries and structures on site
- the achieved storage volumes of the installed retention and detention storages and derivative calculations
- as built locations of all access pits and grates in the detention and retention system(s), including dimensions
- the size of the orifice or control fitted to any on-site detention system
- dimensions of the discharge control pit and access grates
- the maximum depth of storage possible over the outlet control
- top water levels of storage areas and indicative RL's through the overland flow path in the event of blockage of the on-site detention system

The works as executed plan(s) must show the as built details above in comparison to those shown on the drainage plans approved with the Construction Certificate prior to commencement of works. All relevant levels and details indicated must be marked in red on a copy of the Principal Certifying Authority stamped construction certificate stormwater plans.

Reason: To protect the environment.

91. Basement pump-out maintenance

Prior to issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that a maintenance regime has been prepared for the basement stormwater pump-out system.

Note: A maintenance regime specifying that the system is to be regularly inspected and checked by qualified practitioners is to be prepared by a suitable qualified professional and provided to the Principal Certifying Authority.

Reason: To protect the environment.

92. OSD positive covenant/restriction

Prior to issue of the Occupation Certificate, the applicant must create a positive covenant and restriction on the use of land under Section 88E of the Conveyancing Act 1919, burdening the owner with the requirement to maintain the on-site stormwater detention facilities on the lot.

The terms of the instruments are to be generally in accordance with the Council's "draft terms of Section 88B instrument for protection of on-site detention facilities" and to the satisfaction of Council (refer to appendices of Ku-ring-gai Council Water Management DCP 47). For existing titles, the positive covenant and the restriction on the use of land is to be created through an application to the Land Titles Office in the form of a request using forms 13PC and 13RPA. The relative location of the on-site detention facility, in relation to the building footprint, must be shown on a scale sketch, attached as an annexure to the request forms.

Registered title documents, showing the covenants and restrictions, must be submitted and approved by the Principal Certifying Authority prior to issue of an Occupation Certificate.

Reason: To protect the environment.

93. Certification of as-constructed driveway/car park – RFB

Prior to issue of an Occupation Certificate, the Principal Certifying Authority is to be satisfied that:

- the as-constructed car park complies with the approved Construction Certificate plans
- the completed vehicle access and accommodation arrangements comply with Australian Standard 2890.1 – 2004 “Off-Street car parking” in terms of minimum parking space dimensions
- finished driveway gradients and transitions will not result in the scraping of the underside of cars
- no doors, gates, grilles or other structures have been provided in the access driveways to the basement car park, which would prevent unrestricted access for internal garbage collection from the basement garbage storage and collection area
- the vehicular headroom requirements of:
 - Australian Standard 2890.1 – “Off-street car parking”,
 - 2.44 metres height clearance for waste collection trucks (refer DCP 40) are met from the public street into and within the applicable areas of the basement car park.

Note: Evidence from a suitably qualified and experienced traffic/civil engineer indicating compliance with the above is to be provided to and approved by the Principal Certifying Authority prior to the issue of an Occupation Certificate.

Reason: To ensure that vehicular access and accommodation areas are compliant with the consent.

94. Reinstatement of redundant crossings and completion of infrastructure works

Prior to issue of the Occupation Certificate, the Principal Certifying Authority must be satisfied that the following works in the road reserve have been completed:

- new concrete driveway crossing in accordance with levels and specifications issued by Council
- removal of all redundant driveway crossings and kerb laybacks (or sections thereof) and reinstatement of these areas to footpath, turfed verge and upright kerb and gutter (reinstatement works to match surrounding adjacent infrastructure with respect to integration of levels and materials)
- full repair and resealing of any road surface damaged during construction
- full replacement of damaged sections of grass verge with a non-friable turf of native variety to match existing

All works must be completed in accordance with the General Specification for the Construction of Road and Drainage Works in Ku-ring-gai Council, dated November 2004. The Occupation Certificate must not be issued until all damaged public infrastructure caused as a result of construction works on the subject site (including

damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub contractors, concrete vehicles) is fully repaired to the satisfaction of Council. Repair works shall be at no cost to Council.

Reason: To protect the streetscape.

95. Infrastructure repair

Prior to issue of the Occupation Certificate, the Principal Certifying Authority must be satisfied that any damaged public infrastructure caused as a result of construction works (including damage caused by, but not limited to, delivery vehicles, waste collection, contractors, sub contractors, concrete vehicles) is fully repaired to the satisfaction of Council Development Engineer and at no cost to Council.

Reason: To protect public infrastructure.

96. Mechanical ventilation

Prior to the issue of the Occupation Certificate, the Principal Certifying Authority shall be satisfied that all mechanical ventilation systems are installed in accordance with Part F4.5 of the Building Code of Australia and comply with Australian Standards AS1668.2 and AS3666 Microbial Control of Air Handling and Water Systems of Building.

Reason: To ensure adequate levels of health and amenity to the occupants of the building.

CONDITIONS TO BE SATISFIED AT ALL TIMES:

97. Outdoor lighting

At all times for the life of the approved development, all outdoor lighting shall not detrimentally impact upon the amenity of other premises and adjacent dwellings and shall comply with, where relevant, AS/NZ1158.3: 1999 Pedestrian Area (Category P) Lighting and AS4282: 1997 Control of the Obtrusive Effects of Outdoor Lighting.

Reason: To protect the amenity of surrounding properties.

98. Car parking

At all times, the visitor car parking spaces are to be clearly identified and are to be for the exclusive use of visitors to the site. On site permanent car parking spaces are not to be used by those other than an occupant or tenant of the subject building. Any occupant, tenant, lessee or registered proprietor of the development site or part thereof shall not enter into an agreement to lease, license or transfer ownership of any car parking spaces to those other than an occupant, tenant or lessee of the building.

These requirements are to be enforced through the following:

- restrictive covenant placed on title pursuant to Section 88B of the Conveyancing Act, 1919
- restriction on use under Section 68 of the Strata Schemes (Leasehold

Development) Act, 1986 to all lots comprising in part or whole car parking spaces

Reason: To ensure adequate provision of visitor parking spaces.

GB.3 **Community Information Session - St Ives Town Centre**

BUSINESS WITHOUT NOTICE - MATTERS OF GREAT URGENCY

INSPECTIONS COMMITTEE - SETTING OF TIME, DATE AND RENDEZVOUS

CONFIDENTIAL BUSINESS TO BE DEALT WITH IN CLOSED SESSION - PRESS & PUBLIC EXCLUDED

** ** ** ** **

**Environmental Planning & Assessment Act 1979
(as amended)**

Section 79C

1. *Matters for consideration - general*

In determining a development application, a consent authority is to take into consideration such of the following matters as are of relevance to the development the subject of the development application:

a. *The provisions of:*

- i. any environmental planning instrument, and*
- ii. any draft environmental planning instrument that is or has been placed on public exhibition and details of which have been notified to the consent authority, and*
- iii. any development control plan, and*
- iv. any matters prescribed by the regulations,*

that apply to the land to which the development application relates,

- b. the likely impacts of that development, including environmental impacts on both the natural and built environments, and social and economic impacts in the locality,*
- c. the suitability of the site for the development,*
- d. any submissions made in accordance with this Act or the regulations,*
- e. the public interest.*